

SCHEDULE OF QUANTITIES

78300100 PAVEMENT MARKING REMOVAL

LOCATION	STATION	TO	STATION	LENGTH (FT)	QUANTITY (SQ FT)
EASTBOUND	C.L.	878+50.00	961+00.00	2080.00	693.33
EASTBOUND	D.L.	878+50.00	961+00.00	8250.00	2750.00
EASTBOUND	P.L.	878+50.00	961+00.00	8250.00	2750.00
WESTBOUND	C.L.	878+50.00	961+00.00	2080.00	693.33
WESTBOUND	D.L.	878+50.00	961+00.00	8250.00	2750.00
WESTBOUND	P.L.	878+50.00	961+00.00	8250.00	2750.00
TOTAL =					12386.67
USE =					12390.00
					SQ FT

X0327693 HIGH FRICTION SURFACE TREATMENT

LOCATION	STATION	TO	STATION	LENGTH (FT)	AVERAGE WIDTH (FT)	HIGH FRICTION SURFACE TREATMENT (SQ YD)
EASTBOUND	D.L.	878+50.00	961+00.00	8250.00	12.00	11000.00
EASTBOUND	P.L.	878+50.00	961+00.00	8250.00	12.00	11000.00
WESTBOUND	D.L.	878+50.00	961+00.00	8250.00	12.00	11000.00
WESTBOUND	P.L.	878+50.00	961+00.00	8250.00	12.00	11000.00
TOTAL =						44000.00
						SQ YD

X4510050 HIGH FRICTION SURFACE TREATMENT CRACK FILLING

LOCATION	STATION	TO	STATION	PROJECT LENGTH (FT)	MISCELLANEOUS LONGITUDINAL CRACKS (FT)	TRANSVERSE CRACKS (FT)	QUANTITY (FT)
EASTBOUND	878+50.00		961+00.00	8250.00	8250.00	1980.00	10230.00
WESTBOUND	878+50.00		961+00.00	8250.00	8250.00	1980.00	10230.00
TOTAL =							20460.00
							FT

***NOTE:**

HIGH FRICTION SURFACE TREATMENT CRACK FILLING WILL NOT BE REQUIRED ALONG THE EDGE OF PAVEMENT AND SHOULDER JOINT. THE MATERIAL SHALL BE USED FOR ONLY THE MISCELLANEOUS LONGITUDINAL AND TRANSVERSE CRACKS.

70300100 SHORT TERM PAVEMENT MARKING

70301000 WORK ZONE PAVEMENT MARKING REMOVAL

				70300100	70301000
LOCATION	STATION	TO	STATION	QUANTITY (FT)	QUANTITY (SQ FT)
EASTBOUND	D.L. SHLDR	878+50.00	961+00.00	336.00	112.00
EASTBOUND	P.L. SHLDR	878+50.00	961+00.00	336.00	112.00
WESTBOUND	D.L. SHLDR	878+50.00	961+00.00	336.00	112.00
WESTBOUND	P.L. SHLDR	878+50.00	961+00.00	336.00	112.00
TOTAL =				1344.00	448.00
				FT	SQ FT

78009004 MODIFIED URETHANE PAVEMENT MARKING - LINE 4"

LOCATION	STATION	TO	STATION	LENGTH (FT)	COLOR
EASTBOUND	C.L.	878+50.00	961+00.00	2080.00	WHITE
EASTBOUND	D.L.	878+50.00	961+00.00	8250.00	WHITE
EASTBOUND	P.L.	878+50.00	961+00.00	8250.00	YELLOW
WESTBOUND	C.L.	878+50.00	961+00.00	2080.00	WHITE
WESTBOUND	D.L.	878+50.00	961+00.00	8250.00	WHITE
WESTBOUND	P.L.	878+50.00	961+00.00	8250.00	YELLOW
TOTAL =				37160.00	
				FT	

78100100 RAISED REFLECTIVE PAVEMENT MARKER

78300200 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

					78100100	78300200
LOCATION	STATION	TO	STATION	LENGTH (FT)	ONE-WAY CRYSTAL QUANTITY (EACH)	RRPM REMOVAL QUANTITY (EACH)
EASTBOUND	C.L.	878+50.00	961+00.00	8250.00	210.0	210.0
WESTBOUND	C.L.	878+50.00	961+00.00	8250.00	210.0	210.0
TOTAL =					420.0	420.0
					EACH	EACH

X7015005 CHANGEABLE MESSAGE SIGN

LOCATION	PUBLIC NOTIFICATION (CAL DA)	HIGH FRICTION SURFACE TREATMENT OPERATIONS (CAL DA)	TOTAL QUANTITY (CAL DA)
FAI-74 E.B.	7.0	5.0	12.0
FAI-74 W.B.	7.0	5.0	12.0
TOTAL =			24.0
			CAL DA