

PAVEMENT MARKING SCHEDULE			LENGTH	SHORT TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL	PAVEMENT MARKING REMOVAL	TEMPORARY PAVEMENT MARKING - LINE 4"	TEMPORARY PAVEMENT MARKING - LINE 6"	PREFORMED PLASTIC PAVEMENT MARKING, TY B - INLAID - LINE 6"	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	GROOVING FOR RECESSED PAVEMENT MARKING, 5"	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	GROOVING FOR RECESSED PAVEMENT MARKING, 9"	RAISED REFLECTIVE PAVEMENT MARKERS	DELINEATOR REMOVAL	DELINEATORS
STATION TO	STATION	FOOT	FOOT	SQ FT	SQ FT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	EACH	EACH	EACH
EASTBOUND																
656+13	TO 687+86	3173	444	148.1	2512.0	6433	793	793	6433	6433	0	0	0	79	10	10
687+86	TO 692+03	417	42	13.9	330.1	834	104	104	417	417	417	417	417	10	1	1
692+03	TO 712+23	2020	283	94.3	1599.2	4257	505	505	4257	4257	0	0	0	51	10	10
712+23	TO 716+56	433	43	14.4	342.8	866	108	108	433	433	433	433	433	11	1	1
716+56	TO 874+10	15754	2206	735.2	12471.9	31616	3939	3939	31616	31616	0	0	0	394	42	42
874+10	TO 878+10	400	40	13.3	316.7	800	100	100	400	400	400	400	400	10	1	1
878+10	TO 920+50	4240	593	197.9	3356.7	8480	1060	1060	8480	8480	0	0	0	106	11	11
920+50	TO 925+70	520	52	17.3	411.7	1040	130	130	520	520	520	520	520	13	1	1
925+70	TO 1043+60	11790	1651	550.2	9333.8	23863	2948	2948	23863	23863	0	0	0	295	36	36
EB TOTALS:		-	5354	1785	30675	78189	9687	9687	76419	76419	1770	1770	1770	969	113	113
WESTBOUND																
656+13	TO 693+47	3734	523	174.3	2956.1	7686	934	934	7686	7686	0	0	0	93	14	14
693+47	TO 697+72	425	42	14.2	336.5	850	106	106	425	425	425	425	425	11	1	1
697+72	TO 718+10	2038	285	95.1	1613.4	4076	510	510	4076	4076	0	0	0	51	5	5
718+10	TO 722+10	400	40	13.3	316.7	800	100	100	400	400	400	400	400	10	1	1
722+10	TO 1043+60	32150	4501	1500.3	25452.1	64386	8038	8038	64386	64386	0	0	0	804	83	83
WB TOTALS:		-	5391	1797	30675	77798	9687	9687	76973	76973	825	825	825	969	104	104
RAMPS																
RAMP A		1453	99	33.1	825.0	2905	0	0	2480	2480	425	425	425	0	12	12
RAMP B		1387	95	31.7	972.0	2775	0	0	2375	2375	400	400	400	0	14	14
RAMP C		1458	99	33.1	925.0	2916	0	0	2483	2483	433	433	433	0	14	14
RAMP D		1243	83	27.4	968.3	2475	0	0	2058	2058	417	417	417	0	14	14
WEIGH STATION EXIT		430	20	6.5	295.7	887	0	0	487	487	400	400	400	0	5	5
WEIGH STATION ENTRANCE		1738	118	39.4	1158.7	3476	0	0	2956	2956	520	520	520	0	16	16
RAMP TOTALS:		-	514	171	5145	15434	0	0	12839	12839	2595	2595	2595	0	75	75
PROJECT TOTALS:		-	11259	3753	66494	171421	19374	19374	166231	166231	5190	5190	5190	1938	292	292