

PAVING SCHEDULE

STATION	TO	STATION	LENGTH FEET	PAVEMENT WIDTH FEET	SHOULDER WIDTH FEET	AREA SQ YD	BITUMINOUS MATERIALS (PRIME COAT) POUND	POLYMERIZED HOT MIX ASPHALT SURFACE COURSE, MIX "D", N90 TON	POLYMERIZED HOT MIX ASPHALT BINDER COURSE, IL-19.0, N90 TON	HOT MIX ASPHALT SHOULDERS 3/4" TON	SHOULDER RUMBLE STRIPS FOOT	AGGREGATE WEDGE SHOULDERS, TYPE B TON
860+90.00	TO	861+36.68	46.7	48.0	32.0	249.0	280.1	20.9	31.4	34.9	186.7	95.7
861+36.68(BK)	=	126+68.00(AH)	0.0	48.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
126+68.00	TO	128+77.50	209.5	48.0	32.0	1,117.3	1,257.0	93.9	140.8	156.4	838.0	429.5
128+77.50	TO	130+48.84	171.3	48.0	0.0	0.0	0.0	76.8	115.1	0.0	0.0	0.0
130+48.84	TO	132+24.03	175.2	48.0	32.0	934.3	1,051.1	78.5	117.7	130.8	700.8	359.1
132+24.03	TO	135+40.81	316.8	48.0	16.0	1,689.5	1,900.7	141.9	212.9	118.3	950.3	487.0
135+40.81	TO	141+15.80	575.0	48.0	12.0	3,066.6	3,449.9	257.6	386.4	161.0	1,150.0	589.4
141+15.80	TO	141+85.10	69.3	48.0	16.0	369.6	415.8	31.0	46.6	25.9	207.9	71.0
141+85.10	TO	142+03.60	18.5	48.0	32.0	98.7	111.0	8.3	12.4	13.8	37.0	19.0
142+03.60	TO	143+09.10	105.5	48.0	32.0	562.7	633.0	47.3	70.9	78.8	316.5	162.2
143+09.10	TO	148+90.20	581.1	48.0	32.0	3,099.2	3,486.6	260.3	390.5	433.9	2,324.4	1,191.3
148+90.20	TO	149+18.20	28.0	48.0	32.0	149.3	168.0	12.5	18.8	20.9	112.0	43.1
149+18.20	TO	150+35.10	116.9	48.0	32.0	623.5	701.4	52.4	78.6	87.3	350.7	179.7
150+35.10	TO	150+84.13	49.0	48.0	22.0	261.5	294.2	22.0	32.9	25.2	98.1	75.4
150+84.13	TO	151+45.40	61.3	48.0	12.0	326.8	367.6	27.4	41.2	17.2	122.5	62.8
151+45.40	TO	151+45.77	0.4	48.0	12.0	2.0	2.2	0.2	0.2	0.1	0.7	0.4
151+45.77	TO	154+43.55	297.8	48.0	12.0	1,588.2	1,786.7	133.4	200.1	83.4	595.6	305.2
154+43.55	TO	154+76.10	32.6	48.0	12.0	173.6	195.3	14.6	21.9	9.1	65.1	33.4
154+76.10	TO	155+05.15	29.0	48.0	12.0	154.9	174.3	13.0	19.5	8.1	58.1	29.8
155+05.15	TO	155+54.10	49.0	48.0	12.0	261.1	293.7	21.9	32.9	13.7	97.9	50.2
155+54.10	TO	156+72.30	118.2	48.0	22.0	630.4	709.2	53.0	79.4	60.7	354.6	181.7
156+72.30	TO	156+99.30	27.0	48.0	22.0	144.0	162.0	12.1	18.1	13.9	81.0	41.5
156+99.30	TO	162+78.70	579.4	48.0	32.0	3,090.1	3,476.4	259.6	389.4	432.6	2,317.6	1,187.8
162+78.70	TO	163+88.80	110.1	48.0	32.0	587.2	660.6	49.3	74.0	82.2	330.3	169.3
163+88.80	TO	163+96.80	8.0	48.0	22.0	42.7	48.0	3.6	5.4	4.1	16.0	8.2
163+96.80	TO	165+36.00	139.2	48.0	22.0	742.4	835.2	62.4	93.5	71.5	278.4	142.7
165+36.00	TO	170+48.47	512.5	48.0	12.0	2,733.2	3,074.8	229.6	344.4	143.5	1,024.9	525.3
170+48.47	TO	173+64.85	316.4	48.0	22.0	1,687.4	1,898.3	141.7	212.6	162.4	949.1	486.4
173+64.85	TO	211+50.00	3,785.2	48.0	32.0	20,187.5	22,710.9	1,695.7	2,543.6	2,826.2	15,100.6	7,759.6
211+50.00	TO	233+95.54	2,245.5	48.0	32.0	11,976.2	13,473.2	1,006.0	1,509.0	1,676.7	8,942.2	4,603.4
233+95.54	TO	235+01.92	106.4	48.0	0.0	567.4	638.3	0.0	0.0	0.0	0.0	0.0
235+01.92	TO	255+53.34	2,051.4	48.0	32.0	10,940.9	12,308.5	919.0	1,378.6	1,531.7	8,205.7	4,205.4
255+53.34	TO	257+18.34	165.0	48.0	32.0	880.0	990.0	73.9	110.9	123.2	660.0	338.3
257+18.34	TO	259+57.08	238.7	48.0	32.0	1,273.3	1,432.4	53.5	80.2	178.3	955.0	489.4
259+57.08	TO	261+22.08	165.0	48.0	32.0	880.0	990.0	73.9	110.9	123.2	660.0	338.3
261+22.08	TO	321+88.66	6,066.6	48.0	32.0	32,355.1	36,399.5	2,717.8	4,076.7	4,529.7	24,266.3	12,436.5
SHEET TOTALS			19,567			103,445	116,376	8,665	12,998	13,378	72,354	1,374

FILE NAME :	USER NAME : staffnmk	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\puidot\staffnmk\d0106637\07	4470-sht-schudgn	DRAWN -	REVISED -						72	58-64, 65RS-1	MACON	47	11
Default	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -		SCALE: N/A SHEET 1 OF 10 SHEETS STA. TO STA.				CONTRACT NO. 74470				
	PLOT DATE = 6/13/2014	DATE -	REVISED -		ILLINOIS FED. AID PROJECT								