

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	100% STATE										
				ROADWAY		CH 4 OVER I-64	I-64 OVER KASKASKIA RIVER		I-64 OVER OVERFLOW CHANNEL		I-64 OVER PLUM CREEK		TR 68 OVER I-64	
				0005	RURAL	BRIDGE 0014	BRIDGE 0014	BRIDGE 0014	BRIDGE 0014	BRIDGE 0014	BRIDGE 0014	BRIDGE 0014	BRIDGE 0014	
						095-0036	095-0039	095-0040	095-0041	095-0042	095-0043	095-0044	095-0045	
				01		01	02	02	03	03	04	04	05	
28100105	STONE RIPRAP, CLASS A3	SQ YD	33										33	
28200200	FILTER FABRIC	SQ YD	33										33	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	8601	8601										
40600990	TEMPORARY RAMP	SQ YD	758	758										
40603092	HOT-MIX ASPHALT BINDER COURSE, IL-19.0 FG, N90	TON	189	189										
40603243	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, FG, N90	TON	30455	30455										
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	25	25										
40603570	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N90	TON	28391	28391										
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	403285	403285										
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	3276	3276										
44004250	PAVED SHOULDER REMOVAL	SQ YD	322	322										
44200565	CLASS A PATCHES, TYPE II, 11 INCH	SQ YD	89	89										
44200569	CLASS A PATCHES, TYPE III, 11 INCH	SQ YD	23	23										
44200571	CLASS A PATCHES, TYPE IV, 11 INCH	SQ YD	46	46										

FILE NAME = c:\pwork\work\dot\conoverpj\0814571B\0814571B.dgn  
 USER NAME = conoverpj  
 DESIGNED -  
 DRAWN -  
 PLOT SCALE = 100,0000 / 1" =  
 PLOT DATE = 6/13/2014  
 CHECKED -  
 DATE -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES  
 SCALE: SHEET 1 OF 8 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	95-1,21RS-1	WASHINGTON	126	3
CONTRACT NO. 76D20				
ILLINOIS FED. AID PROJECT				