

MAINLINE RESURFACING									
LOCATION	HMA SURFACE REMOVAL - BUTT JOINT	TEMPORARY RAMP	HMA SURFACE REMOVAL, 1 1/2"	HMA SURFACE REMOVAL, 2"	POLYMER BITUMINOUS MATERIALS (PRIME COAT)	BITUMINOUS MATERIALS (PRIME COAT)	POLYMER HMA SURFACE COURSE, MIX E, N90, 2"	POLYMER HMA BINDER COURSE, IL 19.0 FG, N90, 2.25"	HMA SURFACE MIX "C", N70, 2"
WESTBOUND	SQ YD	SQ YD	SQ YD	SQ YD	POUND	POUND	TON	TON	TON
Sta. 1854+60 - 1865+00	307.1	26.7	1696.0		1351.7		243.7	213.7	
Sta. 1865+00 - 1879+00	614.5	53.4	2213.3		1908.9		355.3	278.9	
Sta. 1879+00 - 1893+00			3733.3		2520.0		418.1	470.4	
Sta. 1893+00 - 1955+00			3912.1		2640.6		438.2	492.9	
Sta. 1955+00 - 1970+00			4000.0		2700.0		448.0	504.0	
Sta. 1970+00 - 1985+00			4000.0		2700.0		448.0	504.0	
Sta. 1985+00 - 1998+00			3466.7		2340.0		388.3	436.8	
Sta. 1998+00 - 2013+00	623.8	53.4	2949.3		2406.1		439.4	371.6	
Sta. 2013+00 - 2028+00			4000.0		2700.0		448.0	504.0	
Sta. 2028+00 - 2043+00			4000.0		2700.0		448.0	504.0	
Sta. 2043+00 - 2058+00			3349.3	650.7	2700.0		448.0	504.0	
Sta. 2058+00 - 2073+00			4000.0		2700.0		448.0	504.0	
Sta. 2073+00 - 2088+00			4000.0		2700.0		448.0	504.0	
Sta. 2088+00 - 2103+00			4000.0		2700.0		448.0	504.0	
Sta. 2103+00 - 2118+00			4000.0		2566.1		448.0	371.7	
Sta. 2118+00 - 2133+00			4000.0		2700.0		448.0	504.0	
Sta. 2133+00 - 2148+00			4000.0		2700.0		448.0	504.0	
Sta. 2148+00 - 2163+00			4000.0		2700.0		448.0	504.0	
Sta. 2163+00 - 2178+00			4000.0		2700.0		448.0	504.0	
Sta. 2178+00 - 2193+00			4000.0		2700.0		448.0	504.0	
Sta. 2193+00 - 2208+00			4000.0		2700.0		448.0	504.0	
Sta. 2208+00 - 2223+00			4000.0		2700.0		448.0	504.0	
Sta. 2223+00 - 2238+00			4000.0		2700.0		448.0	504.0	
Sta. 2238+00 - 2253+00			4000.0		2700.0		448.0	504.0	
Sta. 2253+00 - 2268+00			4000.0		2700.0		448.0	504.0	
Sta. 2268+00 - 2283+00			3413.3	586.7	2592.0		448.0	406.6	
Sta. 2283+00 - 2298+00			4000.0		2700.0		448.0	504.0	
Sta. 2298+00 - 2313+00			4000.0		2700.0		448.0	504.0	
Sta. 2313+00 - 2328+00			4000.0		2700.0		448.0	504.0	
Sta. 2328+00 - 2343+00			4000.0		2700.0		448.0	504.0	
Sta. 2343+00 - 2349+10	293.3	26.7	1333.3		954.0		200.6	168.0	
SUBTOTALS	1838.7	160.2	114066.6	1237.4	78679.4	0.00	13235.6	14298.6	0.0