

MAINLINE RESURFACING									
LOCATION	HMA SURFACE REMOVAL - BUTT JOINT	TEMPORARY RAMP	HMA SURFACE REMOVAL, 1 1/2"	HMA SURFACE REMOVAL, 2"	POLYMER BITUMINOUS MATERIALS (PRIME COAT)	BITUMINOUS MATERIALS (PRIME COAT)	POLYMER HMA SURFACE COURSE, MIX E, N90, 2"	POLYMER HMA BINDER COURSE, IL 19.0 FG, N90, 2.25"	HMA SURFACE MIX "C", N70, 2"
	SQ YD	SQ YD	SQ YD	SQ YD	POUND	POUND	TON	TON	TON
IL 177 Ramp A	340.3	66.7	4141.4		2248.2		523.4	521.8	
IL 177 Ramp B	448.4	77.8	3195.5		2374.9		436.4	402.6	
IL 177 Ramp C	416.3	83.3	3196.6		2346.5		430.9	403.5	
IL 177 Ramp D	327.0	111.2	4139.2		2952.3		520.7	521.6	
CH 4	222.2	44.4				150.0			24.8
SUBTOTALS (P. 3)	1754.2	383.4	14672.7	0.0	9921.9	150.0	1911.4	1849.5	24.8
SUBTOTALS (P. 2)	1838.7	160.2	114066.6	1237.4	78679.4	0.0	13235.6	14298.6	0.0
SUBTOTALS (P. 1)	1945.6	213.6	114212.2	728.0	78574.9	0.0	13243.6	14306.8	0.0
TOTALS	5538.5	757.2	242951.5	1965.4	167176.2	150.0	28390.6	30454.9	24.8

FILE NAME =	USER NAME = conoverpj	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
et:\pw\work\p\dot\conoverpj\d0145718\d876d20-sh-t-schedule.dgn	DRAWN -	REVISED -	64					95-(1,2)RS-1	WASHINGTON	126	15	
PLOT SCALE = 100.0000' / 1in.	CHECKED -	REVISED -	SCALE: SHEET NO. 3 OF 13 SHEETS STA. TO STA.			CONTRACT NO. 76D20						
PLOT DATE = 6/13/2014	DATE -	REVISED -	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT									