

CLASS A PAVEMENT PATCHING 11 INCH SCHEDULE											
LOCATION	LANE	LENGTH	LANE WIDTH	CLASS A PATCH TYPE I	CLASS A PATCH TYPE II	CLASS A PATCH TYPE III	CLASS A PATCH TYPE IV	PATCHING REINF.	TIE BARS 3/4"	SAWCUT	
		(FT)	(FT)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(EACH)	(FT)	
EASTBOUND I-64											
2017	+	30	DRIVING	30.0	12.0		40.0	40.0	14	108.0	
2022	+	58	DRIVING	6.0	12.0	8.0		8.0		60.0	
2038	+	42	DRIVING	6.0	12.0	8.0		8.0		60.0	
2043	+	70	DRIVING	6.0	12.0	8.0				60.0	
2043	+	84	DRIVING	6.0	12.0	8.0				60.0	
2043	+	99	DRIVING	15.0	12.0		20.0			78.0	
2044	+	14	DRIVING	10.0	12.0	13.3				68.0	
2075	+	39	DRIVING	6.0	12.0	8.0				60.0	
2107	+	6	DRIVING	6.0	12.0	8.0				60.0	
2112	+	35	DRIVING	6.0	12.0	8.0				60.0	
2228	+	51	DRIVING	6.0	12.0	8.0				60.0	
SUBTOTAL:						77.3	20.0	40.0	56.0	14.0	734.0
ANTICIPATED FAILURES (15%):						11.6	3.0	6.0	17.0	3.0	110.1
TOTAL:						89	23	46	73	17	844

LOCATION	LENGTH	WIDTH	LONGITUDINAL PARTIAL DEPTH REMOVAL, 2"	LONGITUDINAL PARTIAL DEPTH PATCHING
			FOOT	TON
RAMP A	275	2	275	6.8
RAMP B	150	2	150	3.7
RAMP C	175	2	175	4.4
RAMP D	275	2	275	6.8
TOTALS			875	21.7

CLASS B PAVEMENT PATCHING 11 INCH SCHEDULE											
LOCATION	LANE	LENGTH	LANE WIDTH	CLASS B PATCH TYPE I	CLASS B PATCH TYPE II	CLASS B PATCH TYPE III	CLASS B PATCH TYPE IV	DOWEL BARS 1 1/2"	TIE BARS	PAVEMENT FABRIC	SAWCUT
		(FT)	(FT)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(EACH)	(EACH)	(SQ YD)	(FT)
IL 177 - RAMP C											
305	+	52	RAMP	6.0	16.0	10.7		28			60.0
IL 177 - RAMP D											
407	+	50	RAMP	15.0	10.0		16.7	20		16.7	60.0
SUBTOTAL:						10.7	16.7	48		16.7	120.0
ANTICIPATED FAILURES (15%):						1.6	2.5	8	0	2.5	18.0
TOTAL:						12	19	56		19	138