

# SUMMARY OF QUANTITIES

COUNTY:	JOHNSON
ROUTE:	FAP 881 (US 45)
FUNDING:	100% STATE
LOCATION:	RURAL
TOTAL QUANTITY	ROADWAY 0005

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	
40600647	LEVELING BINDER (MACHINE METHOD), IL-9.5FG, N90	TON	7,570	7,570
40600990	TEMPORARY RAMP	SQ YD	86	86
40603320	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N90	TON	15,103	15,103
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	178,951	178,951
44200156	PAVEMENT PATCHING, TYPE II, 13 INCH	SQ YD	1,000	1,000
44200160	PAVEMENT PATCHING, TYPE III, 13 INCH	SQ YD	35	35
44200162	PAVEMENT PATCHING, TYPE IV, 13 INCH	SQ YD	178	178
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	122,522	122,522
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	2,132	2,132
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	10	10
67100100	MOBILIZATION	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\p\dat\brandonja\0335679\701336-rtt-ovr-req.ind.dgn		DRAWN -	REVISED -			881	*	JOHNSON	16	5
		CHECKED -	REVISED -							
		DATE -	REVISED -							
#MODELNAME#	PLOT DATE = 6/13/2014									
					SCALE:	SHEET	OF	SHEETS	STA.	TO STA.

\*34(RS-5),35(RS-3),36(RS-4)  
ILLINOIS FED. AID PROJECT