

-CONT. RESURFACING SCHEDULE

LOCATION				LENGTH	WIDTH	AREA	HMA SURFACE REMOVAL 2 1/4"	HMA SURF CSE MIX "C", N90	HMA LEVELING BINDER, N90, IL-9.5MM FG	BIT MAT PRIME COAT	AGG SHLDRS TYPE B	STRIP REFLECTIVE CRACK CONTROL	TEMPORARY RAMP
				FOOT	FOOT	SQ FT	SQ YD	TON	TON	POUND	TON	FOOT	SQ YD
1537+93.4		TO	1545+00.	706.60	24	16958.4	1884.3	159.1	79.8	1271.9	24.6	1413.2	
1545+00.		TO	1548+90.	390.00	25.75	10042.5	1115.8	94.2	47.2	753.2	13.6	780.0	
1548+90.		TO	1555+54.29	664.29	24	15942.96	1771.4	149.6	75.0	1195.7	23.1	1328.6	20.0
1555+54.29		TO	1557+50.98	OMISSION - SN 044-0055									
1557+50.98		TO	1558+15.	64.02	24	1536.48	170.7	14.4	7.2	115.2	2.2	128.0	20.0
1558+15.		TO	1561+40.	325.00	25.75	8368.75	929.9	78.5	39.3	627.7	11.3	650.0	
1561+40.		TO	1565+98.14	458.14	27.5	12598.85	1399.9	118.1	59.2	944.9	15.9	916.3	
1565+98.14		TO	1566+01.56	3.42	25.75	88.065	9.8	0.8	0.4	6.6	0.1	6.8	
1566+01.56		TO	1569+94.	392.44	24	9418.56	1046.5	88.4	44.3	706.4	13.7	784.9	
1569+94.		TO	1578+24.3	830.30	25.75	21380.225	2375.6	200.5	100.5	1603.5	28.9	1660.6	
1578+24.3	BK =	TO	1586+92.7	57.30	25.75	1475.475	163.9	13.8	6.9	110.7	2.0	114.6	
1586+92.7		TO	1587+50.	167.00	27.5	4592.5	510.3	43.1	21.6	344.4	5.8	334.0	22.9
1587+50.		TO	1589+17.										
<b>TOTAL</b>				61261			178951	15103	7570	120792	2132	122522	86

\*34(RS-5),35(RS-3),36(RS-4)