

PAVEMENT MARKING SCHEDULE

LOCATION					THERMOPLASTIC PAVEMENT MARKING				TEMPORARY PAVEMENT MARKING		SHORT-TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL
					LINE - 4" YELLOW		LINE - 4" WHITE		YELLOW LINE 4"	WHITE LINE 4"				
US 45					LEFT SOLID	RIGHT SOLID	SKIP DASH	SOLID	FOOT	FOOT	FOOT	SQ FT	EACH	EACH
1341+70.		TO	1344+52.				71	564	71	564	85	239.7	4	4
1344+52.		TO	1353+59.			907	227	1,814	1,134	1,814	272	1073.3	12	12
1353+59.		TO	1368+53.7	BK =	1,495	1,495		2,989	2,989	2,989	448	2142.4	19	19
1377+35.9	AH	TO	1385+67.4	BK =	832	832		1,663	1,663	1,663	249	1191.8	11	11
1385+67.6	AH	TO	1391+24.		556	556		1,113	1,113	1,113	167	797.5	7	7
1391+24.		TO	1399+15.		791		198	1,582	989	1,582	237	936.0	10	10
1399+15.		TO	1403+08.			393	98	786	491	786	118	465.1	5	5
1403+08.		TO	1412+64.			956	239	1,912	1,195	1,912	287	1131.3	12	12
1412+64.		TO	1418+49.		585	585		1,170	1,170	1,170	176	838.5	8	8
1418+49.		TO	1423+42.06	BK =	493		123	986	616	986	148	583.5	7	7
1423+38.88	AH	TO	1429+25.		586		147	1,172	733	1,172	176	693.6	8	8
1429+25.		TO	1433+50.				106	850	106	850	128	361.3	6	6
1433+50.		TO	1443+75.			1,025	256	2,050	1,281	2,050	308	1212.9	13	13
1443+75.		TO	1473+00.		2,925	2,925		5,850	5,850	5,850	878	4192.5	37	37
1473+00.		TO	1476+96.2	BK =	396	396		792	792	792	119	567.9	5	5
1476+90.	AH	TO	1484+54.		764	764		1,528	1,528	1,528	229	1095.1	10	10
1484+54.		TO	1495+50.		1,096		274	2,192	1,370	2,192	329	1296.9	14	14
1495+50.		TO	1509+67.45	BK =			354	2,835	354	2,835	425	1204.8	18	18
1509+73.12	AH	TO	1537+94.9	BK =			705	5,644	705	5,644	847	2398.5	36	36
1537+93.4	AH	TO	1539+43.				37	299	37	299	45	127.2	2	2
1539+43.		TO	1550+67.			1,124	281	2,248	1,405	2,248	337	1330.1	15	15
1550+67.		TO	1556+39.		572	572		1,144	1,144	1,144	172	819.9	8	8
1556+39.		TO	1578+24.3	BK =	2,185	2,185		4,371	4,371	4,371	656	3132.3	28	28
1586+92.7	AH		1589+17.		224	224		449	449	449	67	321.5	3	3
TOTAL					36,341	36,742	9,094	122,915	82,176	122,915	18,437	74,509	801	801
					205,091				205,091					

-WORK ZONE PAVEMENT MARKING REMOVAL = REMOVAL OF TEMPORARY PAVEMENT MARKING AND SHORT TERM PAVEMENT MARKING

FILE NAME =	USER NAME = \$USER\$	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION		F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
et:\pw\work\p\dot\brandonja\d0335679\78348-sha-cvr-soq-index.dgn		DRAWN -	REVISED -			881	*			16	13
\$MODELNAME\$		CHECKED -	REVISED -			CONTRACT NO. 78348					
	PLOT DATE = 6/13/2014	DATE -	REVISED -			SCALE:	SHEET OF SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT	