



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

September 10, 2015

SUBJECT: FAU Route 8776 (Burrell Street)  
Section 12-00091-00-RS  
White County  
Contract No. 99538  
Item 063  
September 18, 2015 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans and/or the proposal. This addendum involves revised, added and/or deleted material.

### 1. Revised page 3 of the special provisions

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

John Baranzelli, P.E.  
Acting Engineer of Design and Environment

A handwritten signature in black ink, appearing to read 'Ted B. Walschleger' with a small 'P.E.' to the right.

By: Ted B. Walschleger, P.E.  
Engineer of Project Management

be given.

### **REMOVAL OF UNCLASSIFIED MATERIAL**

**Description.** The existing pipe culverts and other unclassified materials such as rubble, tree limbs, rubbish, stones, etc. shall be removed at the locations shown on the plans or as designated by the Engineer. This shall also include the retaining wall for the signal flashing lights located at Station 11+50 on the left side. The material removed as required in this special provision shall be disposed of outside the limits of the right-of-way in accordance with Article 202.03 of the Standard Specifications and as directed by the Engineer.

**Basis of Payment.** This work will not be paid for separately, but will be included in the cost of EARTH EXCAVATION, and no other compensation will be allowed.

### **OVERHAUL**

Overhaul shall not be paid for material moved to or from any source.

### **PORTLAND CEMENT CONCRETE PAVEMENT**

Section 420 of the Standard Specifications shall govern this item of work with the exception that the option of pavement with an integral concrete curb maybe constructed instead of **PORTLAND CEMENT CONCRETE PAVEMENT 8"** and **COMBINATION CONCRETE CURB AND GUTTER** specified. If the concrete pavement with an integral concrete curb is constructed LR 420 SPECIAL PROVISION FOR PORTLAND CONCRETE PAVEMENT (SPECIAL) shall govern this item. Construction of the streets using the integral concrete curb shall still meet the thickness and widths required in the plans. The concrete pavement with an integral concrete curb method shall be paid for using plan quantity for both **PORTLAND CEMENT CONCRETE PAVEMENT 8" (JOINTED)** and **COMBINATION CONCRETE CURB AND GUTTER** specified and no further compensation will be allowed.

### **TRENCH DRAIN**

This work shall consist of trench drains at the location shown on the plans. Trench drains shall include materials necessary to install the trench drain complete, including all associated fittings, cast-in place concrete cradle supporting the fabricated drain system, drain cover, all extension materials, and tie-ins. Trench drains must be connected to the nearest drainage structure and shall be included in the price for **TRENCH DRAIN**.

Trench drains shall be presloped channels constructed with polymer concrete. Grates shall be slotted, stainless steel, load class C with stainless steel locking bar assemblies and countersunk