



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

August 25, 2020

SUBJECT: FAI Route 70 (I-70)/FAI Route 270 (I-270)
Project NHPP-YQT9(213)
Section 60-(10,11)RS-1
Madison County
Contract No. 76H84
Item No. 31, September 18, 2020 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices in ICX only.
2. Revised the Heading to the Special Provisions to include the Federal Project Number.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

STATE OF ILLINOIS

SPECIAL PROVISIONS

The following Special Provisions supplement the "Standard Specifications for Road and Bridge Construction," adopted April 1, 2006, the latest edition of the "Manual on Uniform Traffic Control Devices for Streets and Highways," and the "Manual of Test Procedures for Materials" in effect on the date of invitation for bids, and the Supplemental Specifications and Recurring Special Provisions indicated on the Check Sheet included herein which apply to and govern the construction of FAI Route 70(I-70)/FAI Route 270 (I-270); Project NHPP-YQT9(213); Section 60-(10-11)RS-1; Madison County; Contract No. 76H84 and in case of conflict with any part or parts of said Specifications, the said Special Provisions shall take precedence and shall govern.

LOCATION OF PROJECT

This work involves widening and resurfacing along FAI Route 70 (I-70), FAI Route 270 (I-270), the Triple-I Interchange Ramps, FAI Route 55/70 (I-55/70).

The work along FAI Route 70 (I-70), FAI Route 270 (I-270), and the Triple-I Interchange Ramps is from approximately 0.62 miles south of the Triple-I Interchange along the EB I-70 and WB I-70 to I-55/70 ramps to approximately 2.1 miles east of the interchange northeast of Troy in Madison County, Illinois. In addition, interchange ramps G-1, G-3, G-4, G-5, G-6, and G-7 will be resurfaced.

The work along FAI Route 55/70 (I-55/70) is from 0.3 miles east of IL Route 159 to 0.3 miles north of FAI 270 (I-270) in Madison County.

DESCRIPTION OF PROJECT

Work items for the widening and resurfacing operations along FAI Route 70 (I-70), FAI Route 270 (I-270), and the Triple I Interchange Ramps include pavement patching, hot-mix asphalt removal, widening of pavement and shoulders on FAI Route 70 (I-70), removal and replacement of guardrail and traffic barrier terminals, aggregate shoulders, hot-mix asphalt shoulders, portland cement concrete pavement, hot-mix asphalt binder and surface courses, permanent pavement marking, signing, drainage inlet and pipe drain reconstruction, temporary concrete barrier, impact attenuators, removing a crossover, relocating a crossover, repairing several structures, traffic control and all other necessary and collateral work to complete the project as shown on the plans and as specified elsewhere in these provisions.

Work items for the resurfacing operations along FAI Route 55/70 (I-55/70) includes pavement patching, hot-mix asphalt surface removal, Ultra-Thin Bonded Wearing Surface Course, pavement marking, traffic control and all other necessary and collateral work needed to complete the project as shown in the plans and as specified elsewhere in these provisions.

Revised August 25, 2020