

PROJECT: GATEWAYS AND CORNER GARDENS AT 95TH STREET  
 COOK COUNTY / CITY OF CHICAGO

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	2005-068 LS	COOK	58	4
STA. 153+09 (SB 1-57) TO STA. 2214+95 (SB 1-94)				
STA. 257+76 (NB 1-57) TO STA. 2213+00 (NB 1-94)				
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

60A74

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	URBAN TOTAL	100% STATE		100% CITY OF CHICAGO
				DAN RYAN Y003	DAN RYAN Y007	DAN RYAN Y003
20200100	EARTH EXCAVATION	CU YD	295	295		
21101645	TOPSOIL FURNISH AND PLACE, 12"	SQ YD	472	472		
21101825	COMPOST FURNISH AND PLACE, 6"	SQ YD	472	472		
25000210	SEEDING, CLASS 2A	ACRE	0.75	0.75		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	112	112		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	87	87		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	74	74		
25100630	EROSION CONTROL BLANKET	SQ YD	2581	2581		
25200110	SODDING, SALT TOLERANT	SQ YD	12			12
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	54	54		
28000510	INLET FILTERS	EACH	30	30		
• 42001300	PROTECTIVE COAT	SQ YD	338			338
• 42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	90			90
• 44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	20			20
• 44000600	SIDEWALK REMOVAL	SQ FT	49			49
• 44004250	PAVED SHOULDER REMOVAL	SQ YD	5			5
• 56104600	WATER VALVES 2"	EACH	3			3
• 60600605	CONCRETE CURB, TYPE B	FOOT	222.0	222.0		
• 66410400	CHAIN LINK FENCE TO BE REMOVED AND RE-ERECTED	FOOT	130	130		
67100100	MOBILIZATION	L SUM	1	1		
• 70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1		
▲ 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	42			42
▲ 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	6			6
C2001061	SHRUB, CARYOPTERIS CLANDONENSIS 'LONGWOOD BLUE BLUEBEARD', 1-GALLON	EACH	630	630		
A2007254	TREE, ROBINIA PSEUDOACACIA CHICAGO BLUES (CHICAGO BLUES BLACK LOCUST), 4" CALIPER, BALLED AND BURLAPPED, MATCHING HEADS	EACH	25	25		
B2006385	TREE, SYRINGA VULGARIS PRESIDENT LINCOLN (PRESIDENT LINCOLN LILAC), 5' HEIGHT, BALLED AND BURLAPPED	EACH	21	21		
K0030470	PERENNIAL PLANT, ORNAMENTAL GRASS TYPE	UNIT	43	43		
K1003460	LANDSCAPE MAINTENANCE	CAL MO	11	11		
X0301407	PERENNIAL PLANTS, GALLON POT	UNIT	58	58		

▲ SPECIALTY ITEMS

\* - SPECIAL PROVISIONS

TYLIN INTERNATIONAL

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 F.A.I. 94 (DAN RYAN EXPRESSWAY)  
 SUMMARY OF QUANTITIES  
 SHEET 1 OF 2

SCALE: NONE  
 DATE: JUNE 20, 2008  
 DRAWN BY: JDF  
 CHECKED BY: RTM

P:\023731\000\2220\94\2220\10\3.dwg 12/20/2008 12:00:16 PM