

| | | | | |
|---------------------|---------------------------|--------|--------------|-----------|
| F.A. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| | 06-00353-00-SP | KANE | 7 | 2 |
| CONTRACT NO. 63048 | | | | |
| FED. ROAD DIST. NO. | ILLINOIS FED. AID PROJECT | | | |

SUMMARY OF QUANTITIES
(Construction Type Code Y-031-1F)

| CODE NO. | DESCRIPTION | UNIT | QUANTITY |
|----------|--|-------|----------|
| 67100100 | MOBILIZATION | L SUM | 1 |
| 70101800 | TRAFFIC CONTROL AND PROTECTION (SPECIAL) | L SUM | 1 |
| 72400310 | REMOVE SIGN PANEL - TYPE 1 | SQ FT | 14 |
| 81000500 | CONDUIT IN TRENCH, 1/2" DIA., GALVANIZED STEEL | FOOT | 48 |
| 81018400 | CONDUIT PUSHED, 1/2" DIA., GALVANIZED STEEL | FOOT | 86 |
| 81400200 | HEAVY-DUTY HANDHOLE | EACH | 1 |
| 81900200 | TRENCH AND BACKFILL FOR ELECTRICAL WORK | FOOT | 48 |
| 85000300 | MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION | L SUM | 1 |
| 87301215 | ELECTRIC CABLE IN CONDUIT, NO. 14 2/C | FOOT | 4094 |
| X8730027 | ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C | FOOT | 2090 |
| 87700210 | STEEL MAST ARM ASSEMBLY AND POLE, 34 FT. | EACH | 2 |
| 87800400 | CONCRETE FOUNDATION, TYPE E, 30 INCH DIAMETER | FOOT | 30 |
| 87900200 | DRILL EXISTING HANDHOLE | EACH | 1 |
| X8050015 | SERVICE INSTALLATION - POLE MOUNTED | EACH | 1 |
| 88040010 | SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 1-SECTION, MAST-ARM MOUNTED | EACH | 4 |
| 88200100 | TRAFFIC SIGNAL BACKPLATE | EACH | 4 |
| 89502200 | MODIFY EXISTING CONTROLLER | EACH | 1 |



METRO TRANSPORTATION GROUP, INC.
 TRAFFIC ENGINEERING
 TRANSPORTATION PLANNING/ENGINEERING
 SIGNAL SYSTEMS/DESIGN
 3100 W. HIGGINS ROAD, STE. 100
 HOFFMAN ESTATES, IL 60169-2093
 PH: 630.213.1000, FAX: 630.213.3227
 www.metrotransportation.com

| REVISIONS | | |
|-----------|------|-------------|
| NO. | DATE | DESCRIPTION |
| | | |
| | | |
| | | |

SUMMARY OF QUANTITIES

KANE COUNTY, ILLINOIS

FILE NAME:
02_500.dgn
DATE
June 26, 2008
PROJECT NO.:
H0702.06-100

SHEET NO.:

2
OF 7