

SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	CONST. CODE 1000 TOTAL QUANTITY
21400100	GRADING AND SHAPING DITCHES	FOOT	190
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	4152
40600300	AGGREGATE (PRIME COAT)	TON	32
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	1196
40600895	CONSTRUCTING TEST STRIP	EACH	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	737
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	2787
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	79
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	394
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL & REPLACEMENT	FOOT	90
44201705	CLASS D PATCHES, TYPE II, 5 INCH	SQ YD	13
44201709	CLASS D PATCHES, TYPE III, 5 INCH	SQ YD	41
44201711	CLASS D PATCHES, TYPE IV, 5 INCH	SQ YD	1813
44300100	AREA REFLECTIVE CRACK CONTROL TREATMENT	SQ YD	1000
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	9872
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	320
48203009	HOT-MIX ASPHALT SHOULDERS, 3"	SQ YD	304
67100100	MOBILIZATION	L SUM	1
70101800	TRAFFIC CONTROL & PROTECTION, SPECIAL	L SUM	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2468
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2468
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	823
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	62.4
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	34251
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	138
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	80
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	45
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	55
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	55
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	105
X0322052	ASPHALT REJUVENATING AGENT	GAL	2585
X0324096	HOT IN-PLACE RECYCLING	SQ YD	25832
XX006425	RESTORATION	SQ YD	570

*SPECIALTY ITEMS

Plotted: July 15, 2008 3:05 PM By: Jim Golos - Tab: 03 Sum of Quant 22/34

COPYRIGHT © 2008 ENGINEERING ENTERPRISES, INC.



Engineering Enterprises, Inc.
CONSULTING ENGINEERS
52 Wheeler Road
Sugar Grove, Illinois 60554
Phone: (630) 466-9350

VILLAGE OF SUGAR GROVE
10 MUNICIPAL DRIVE
SUGAR GROVE, IL 60554

NO.	DATE	REVISIONS
2	7/15/08	PER IDOT COMMENTS
1	7/2/08	PER IDOT COMMENTS

WHEELER ROAD LAPP RESURFACING

SUMMARY OF QUANTITIES

DATE:	MAY 2008
PROJECT NO:	SG0825
FILE NO:	SG0825-CVR
SHEET	3 OF 18

Path: H:\SBS\KRCV\SG0825\DWG\DWG_FINAL_ENG\SG0825-CVR