

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
649	28 N & I	LIVINGSTON	6	3
STA.		TO STA.		
FED. ROAD DIST. NO. _		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE:	
				Y031-IF	QOY F.E.D. 10% STATE
67100100	MOBILIZATION	L SUM	1		1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1		1
80500300	SERVICE INSTALLATION, TYPE C	EACH	3		3
81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC	FOOT	1828		1828
81021320	CONDUIT PUSHED, 1 1/2" DIA., PVC	FOOT	495		495
81100500	CONDUIT ATTACHED TO STRUCTURE, 1 1/2" DIA., GALVANIZED STEEL	FOOT	75		75
81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	11		11
81900200	TRENCH BACKFILL FOR ELECTRICAL WORK	FOOT	1828		1828
83057150	LIGHT POLE, WOOD, 30 FOOT, CLASS 4	EACH	1		1
85000500	MAINTENANCE OF EXISTING FLASHING BEACON INSTALLATION	EACH	1		1
85800100	FLASHER CONTROLLER	EACH	3		3
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	2925		2925
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	101		101
88040030	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 1-SECTION, POST MOUNTED	EACH	6		6
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	221		221
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1		1
X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	2434		2434
Z0055300	RUMBLE STRIP	EACH	6		6

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 FAP 649 (IL 17)
 SECTION 28 N & I
 LIVINGSTON COUNTY

SCALE: VERT.
 HORIZ.
 DATE 05/08

DRAWN BY NOE
 CHECKED BY JLS