

SCHEDULE OF PAVEMENT MARKING

LOCATION	PAVEMENT MARKING REMOVAL	EPOXY PAVEMENT MARKING- LETTER AND SYMBOLS		EPOXY PAVEMENT MARKING- LINE 4"		EPOXY PAVEMENT MARKING- LINE 8"		FLEXIBLE DELINEATORS
		SQ FT		FEET		FEET		
		WHITE	YELLOW	WHITE	YELLOW	WHITE	YELLOW	
WEST EXIT	401	12		340	200	332		8
WEST ENTRANCE	224	24		283	186	133		6
EAST ENTRANCE	325	35		182	228	282		7
EAST EXIT	421	12		205	362	348		7
SUBTOTAL	970	83		1010	976	1095		20
TOTAL	970	83		1986		1095		20

SCHEDULE OF SCALE HOUSE FLOOR REPAIR

LOCATION	SUB-FLOOR REMOVAL	SUB-FLOOR INSTALLATION	12" X 12" TILE FLOORING
	SQ FT	SQ FT	SQ FT
REST ROOM			35
ALCOVE			28
UTILITY ROOM			35
ENTRANCE HALL			82
OFFICE AREA	152	152	152
TOTAL	152	152	332

SCHEDULE OF SEEDING

LOCATION	GRADING EXISTING INFIELD	SEEDING CLASS 1A	NITROGEN FERTILIZER NUTRIENT	NITROGEN PHOSPHORUS NUTRIENT	NITROGEN POTASSIUM NUTRIENT	MULCH METHOD 2						
							SQ YD	ACRE	POUND	POUND	POUND	TON
							INFIELD	1651	0.34	20	20	20
TOTAL	1651	0.34	20	20	20	1						

SCHEDULE OF DELINEATORS

LOCATION	DELINEATOR REMOVAL	DELINEATORS
	EACH	EACH
	WEST EXIT	8
WEST ENTRANCE	7	31
EAST EXIT	9	54
EAST ENTRANCE	4	35
TOTAL	28	174

SCHEDULE OF PCC WIDENING

LOCATION		EARTH EXCAVATION (WIDENING)	SUB-BASE GRANULAR MATERIAL TYPE B 4"	TIE BARS	PAVEMENT FABRIC	PCC BASE CSE
						CSE.
						WIDENING 10"
		CU YD	SQ YD	EACH	SQ YD	SQ YD
WEST ENTRANCE	LT	24	61	50	61	61
	RT	27	70	65	70	70
EAST ENTRANCE	LT	31	80	73	80	80
	RT	24	61	50	61	61
EAST EXIT	LT	33	85	61	85	85
	RT					
TOTAL		138	357	299	357	357

SCHEDULE OF HOT-MIX ASPHALT OVERLAY

LOCATION	CONCRETE PAVEMENT SCARIFICATION	BITUMINOUS MATERIALS (PRIME COAT)	HOT-MIX ASPHALT SURFACE CSE.
			MIX C, N90
			TON
	SQ YD	GAL	TON
WEST ENTRANCE	458	37	52
EAST ENTRANCE	640	52	72
TOTAL	1098	89	124

FILE NAME = c:\projects\cm312\details.dgn

USER NAME = carpenterdj

DESIGNED - Ron Woodshank
DRAWN - Ron Woodshank

REVISED -
REVISED -

PLOT SCALE = 100.0000' / IN.
PLOT DATE = Jul 11, 2008 - 01:32:19 PM

CHECKED -
DATE -

REVISED -
REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULES

SCALE: SHEET NO. 2 OF 2 SHEETS STA. TO STA.

* TRUCK WEIGH STATION #17 (I-1)

F.A.P. RTE. 317	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		IROQUOIS	19	7
FED. ROAD DIST. NO. ILLINOIS			CONTRACT NO. 66849	