

S U M M A R Y O F Q U A N T I T I E S

CODE NO.	ITEM	UNIT	MONTGOMERY CO	SANGAMON CO	100% STATE
					K000
					TOTAL QTY
67100100	MOBILIZATION	L SUM	0.5	0.5	1
81017510	CONDUIT IN TRENCH, 1" DIA., COILABLE NONMETALIC CONDUIT	FOOT	125	0	125
81018700	CONDUIT PUSHED, 3" DIA., GALVANIZED STEEL	FOOT	120	0	120
81702130	ELECTRIC CABLE IN CONDUIT, 600V. (XLP-TYPE USE) 1/C NO. 6	FOOT	125	0	125
82105400	LUMINAIRE, SODIUM VAPOR, HIGH MAST, MULTI-MOUNT, 400 WATT	EACH	6	0	6
83502400	LIGHT TOWER, 100 FT. MOUNTING HEIGHT, LUMINAIRE MT.-6	EACH	1	0	1
83700300	LIGHT TOWER FOUNDATION, 48" DIAMETER	FOOT	20	0	20
89502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	250	0	250
X0325378	REMOVE AND REINSTALL LIGHT POLE, COUPLINGS, WITH STAINLESS STEEL SCREENS	EACH	0	25	25
X8420210	REMOVE LIGHT TOWER FOUNDATION, PARTIAL	EACH	1	0	1

QUANTITIES
FAI 55 (I-55)
SECTION D6 LIGHTING 2009
SANGAMON/MONTGOMERY COUNTY

Rev,