

# SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		URBAN 1000 100% STATE	SIGNALS Y031-IF 100% STATE	-----	CODE NO	ITEM	UNIT		URBAN 1000 100% STATE	SIGNALS Y031-IF 100% STATE	-----
20200100	EARTH EXCAVATION	CU YD	284	284		54248510	CONCRETE COLLAR	CU YD	1	1			
20400800	FURNISHED EXCAVATION	CU YD	275	275		55019700	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 18"	FOOT	9	9			
20800150	TRENCH BACKFILL	CU YD	6	6		60600095	CLASS SI CONCRETE (OUTLET)	CU YD	7	7			
*21101685	TOPSOIL FURNISH AND PLACE, 24"	SQ YD	97	97		60603500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.06	FOOT	76	76			
*25000100	SEEDING, CLASS 1	ACRE	0.25	0.25		60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	220	220			
*25000400	NITROGEN FERTILIZER NUTRIENT	POUND	23	23		60605500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (VARIABLE WIDTH GUTTER FLAG)	FOOT	157	157			
*25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	23	23		60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	1565	1565			
*25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	23	23		67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	4	4			
*25100115	MULCH, METHOD 2	ACRE	0.25	0.25		67100100	MOBILIZATION	L SUM	1	1			
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	25	25		70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1			
28000300	TEMPORARY DITCH CHECKS	EACH	9	9		70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1			
28000400	PERIMETER EROSION BARRIER	FOOT	1466	1466		70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	45	45			
28000500	INLET AND PIPE PROTECTION	EACH	1	1		70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	208	208			
28100707	STONE DUMPED RIPRAP, CLASS A4	SQ YD	5	5		70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	3002	3002			
28200200	FILTER FABRIC	SQ YD	5	5		70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	1088	1088			
30200650	PROCESSING MODIFIED SOIL 12"	SQ YD	2752	2752		70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	299	299			
30201500	LIME	TON	68	68		70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2025	2025			
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	1346	1346		*72000100	SIGN PANEL - TYPE 1	SQ FT	26	26			
31100500	SUB-BASE GRANULAR MATERIAL, TYPE A 6"	SQ YD	265	265		*72900100	METAL POST - TYPE A	FOOT	25	25			
31102300	SUB-BASE GRANULAR MATERIAL, TYPE C 6"	SQ YD	486	486		*72900200	METAL POST - TYPE B	FOOT	41	41			
35100100	AGGREGATE BASE COURSE, TYPE A	TON	78	78		*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1600	1600			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.3	0.3		*78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	229	229			
40603090	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	685	685		*78003100	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS AND SYMBOLS	SQ FT	208	208			
40603570	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N90	TON	108	108		*78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	1402	1402			
42000301	PORTLAND CEMENT CONCRETE PAVEMENT 8" (JOINTED)	SQ YD	1172	1172		*78008240	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT	859	859			
42001200	PAVEMENT FABRIC	SQ YD	1172	1172		*78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	299	299			
42001300	PROTECTIVE COAT	SQ YD	1521	1521		*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	25	25			
44000100	PAVEMENT REMOVAL	SQ YD	119	119		*78200300	PRISMATIC CURB REFLECTOR	EACH	29	29			
44000400	GUTTER REMOVAL	FOOT	87	87									
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	275	275									
44004250	PAVED SHOULDER REMOVAL	SQ YD	966	966									
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	651	651									
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1	1									

FILE NAME =	USER NAME = conoverpj	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ca:\projects\ed01808\plan\plan01808a.dgn		DRAWN -	REVISED -			592	65I-TS-1	MADISON	50	3
	PLOT SCALE = 50.0000" = 1" IN.	CHECKED -	REVISED -			CONTRACT NO. 76B41				
	PLOT DATE = 7/9/2008	DATE -	REVISED -			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

\*Specialty Items Rev.