

CODE NO.	DESCRIPTION	UNIT	TOTAL QTY	ROADWAY 1000-2A	Y030-1E	Y031-1F	100% NORTH CHICAGO Y060
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	169	169			
20101100	TREE TRUNK PROTECTION	EACH	26	26			
20200100	EARTH EXCAVATION	CU YD	11,613	11,613			
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1,144	1,144			
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	1,000	1,000			
20800150	TRENCH BACKFILL	CU YD	23,249	6,517			16,732
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	8,500	8,500			
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	5,122	5,122			
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	64	64			
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	64	64			
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	64	64			
* 25200110	SODDING, SALT TOLERANT	SQ YD	5,122	5,122			
28000400	PERIMETER EROSION BARRIER	FOOT	11,634	11,634			
28000510	INLET FILTERS	EACH	178	178			
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	6,182	6,182			
35100500	AGGREGATE BASE COURSE, TYPE A 6"	SQ YD	653	653			
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	1,000	1,000			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	17	17			
40600300	AGGREGATE (PRIME COAT)	TON	83	83			
40600535	LEVELING BINDER (HAND METHOD), N70	TON	10	10			
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	85	85			
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	60	60			
40701901	HOT-MIX ASPHALT PAVEMENT, (FULL-DEPTH), 11"	SQ YD	41,700	41,700			
42001300	PROTECTIVE COAT	SQ YD	11,154	11,154			
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	185	185			

CODE NO.	DESCRIPTION	UNIT	TOTAL QTY	ROADWAY 1000-2A	Y030-1E	Y031-1F	100% NORTH CHICAGO Y060
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	1,657	1,657			
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	56,964	56,964			
42400800	DETECTABLE WARNINGS	SQ FT	696	696			
44000100	PAVEMENT REMOVAL	SQ YD	41,700	41,700			
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1,763	1,763			
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	12,955	12,955			
44000600	SIDEWALK REMOVAL	SQ FT	53,042	53,042			
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	4				4
44003100	MEDIAN REMOVAL	SQ FT	280	280			
44201777	CLASS D PATCHES, TYPE II, 11 INCH	SQ YD	9				9
44201783	CLASS D PATCHES, TYPE IV, 11 INCH	SQ YD	321	271			50
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	41	41			
50104600	CONCRETE RETAINING WALL REMOVAL	FOOT	123	123			
50900605	HANDRAIL REMOVAL	FOOT	103	103			
50901760	PIPE HANDRAIL	FOOT	103	103			
550A2190	STORM SEWERS, CLASS A, DRILLED OR PUSHED 36"	FOOT	120	120			
550A2320	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 12"	FOOT	378	378			
550A2360	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 24"	FOOT	62	62			
550A2520	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 12"	FOOT	824	824			
550A2530	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 15"	FOOT	62	62			
550A2540	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 18"	FOOT	52	52			

CONSTRUCTION TYPE CODE: * = SPECIALTY ITEM
(1) = Y080

DATE: 7/9/2008
TIME: 9:38:40 AM
FILENAME: N:\PECO\15161\Design\Misc\Sheets\15161-S00-01.dgn

REVISIONS	
NAME	DATE

Clorba Group, Inc.
CONSULTING ENGINEERS
5507 North Cumberland Avenue, Suite 402 Chicago, Illinois 60656
Tel. 773.775.4009 Fax 773.775.4014 Email chicago@clorba.com

CITY OF NORTH CHICAGO
MARTIN LUTHER KING JR. DRIVE IMPROVEMENTS

SUMMARY OF QUANTITIES

SCALE: N.T.S. DRAWN BY: BWS
DATE: APRIL, 2008 CHECKED BY: MJL