F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1230	03-00159-00-PV	LAKE	262	6
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

CONTRACT: 83828

	CODE NO.	DESCRIPTION	UNIT	TOTAL QTY	ROADWAY I000-2A	Y030-1E	Y031-1F	100% NORTH CHICAGO Y060
	60624600	CORRUGATED MEDIAN	SQ FT	73	73			
	63200310	GUARDRAIL REMOVAL	FOOT	545	545			
	66400305	CHAIN LINK FENCE, 6'	FOOT	1,091	1,091			
*	66900205	SPECIAL WASTE DISPOSAL	CU YD	4,500	3,500			1,000
*	66900210	HAZARDOUS WASTE DISPOSAL	CU YD	700	400			300
*	66900400	SPECIAL WASTE GROUND WATER DISPOSAL	GALLON	18,000				18,000
*	66900425	HAZARDOUS WASTE GROUND WATER DISPOSAL	GALLON	935				935
*	66900450	SPECIAL WASTE PLANS AND REPORT	L SUM	1				1
*	66900530	SOIL DISPOSAL ANALYSIS	EACH	20				20
*	66900535	PRIORITY POLLUTANTS GROUND WATER ANALYSIS	EACH	10				10
*	66901000	BACKFILL PLUGS	CU YD	24				24
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	24	24			
	67100100	MOBILIZATION	L SUM	1	1			
	70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1			
	70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	1			
	70300100	SHORT TERM PAVEMENT MARKING	FOOT	10,000	10,000			
	70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	40,488	40,488			
	70300570	PAVEMENT MARKING TAPE, TYPE III 24"	FOOT	1,105	1,105			
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	14,450	14,450			
	72000100	SIGN PANEL - TYPE 1	SQ FT	258	258			
	72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	50	50			
	72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	5	5			
	72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	9	9			
	72400600	RELOCATE SIGN PANEL ASSEMBLY - TYPE B	EACH	1	1			
	72900100	METAL POST - TYPE A	FOOT	207	207			

	CODE NO.	DESCRIPTION	UNIT	TOTAL QTY	ROADWAY I000-2A	Y030-1E	Y031-1F	100% NORTH CHICAGO Y060
	72900200	METAL POST - TYPE B	FOOT	337	337			
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	468	468			
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	18,359	18,359			
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2,611	2,611			
*	78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	3,372	3,372			
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	897	897			
*	78000610	THERMOPLASTIC PAVEMENT MARKING - LINE 16"	FOOT	405	405			
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	1,105	1,105			
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	470	470			
*	80400100	ELECTRIC SERVICE INSTALLATION	EACH	3		3		
*	80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1		1		
*	81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	3,750		3,750		
*	81400100	HANDHOLE	EACH	21			21	
*	81400300	DOUBLE HANDHOLE	EACH	4			4	
*	81702170	ELECTRIC CABLE IN CONDUIT, 600 V (XLP-TYPE USE) 1/C NO. 2/0	FOOT	840		840		
*	81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	200		200		
*	82102310	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 310 WATT	EACH	8		8		
*	82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	8		8		
*	82103650	LUMINAIRE, SODIUM VAPOR, VERTICAL MOUNT, 310 WATT	EACH	82		82		
*	82500530	LIGHTING CONTROLLER CB-RCS 100 AMP-240 VOLT	EACH	3		3		
*	83009600	LIGHT POLE, ALUMINUM, 45 FT. M.H., 15 FT. MAST ARM	EACH	8		8		
*	83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	450		450		

CONSTRUCTION TYPE CODE: * = SPECIALTY ITEM
(1) = Y080

REVISIONS	
NAME	DATE

Ciorba Group, Inc.
CONSULTING ENGINEERS
5507 North Cumberland Avenue, Suite 402 Chicago, Illinois 60656
Tel. 773.775.4009 Fax 773.775.4014 Email chicago@ciorba.com

CITY OF NORTH CHICAGO
MARTIN LUTHER KING JR. DRIVE IMPROVEMENTS

SUMMARY OF QUANTITIES

SCALE: N.T.S. DRAWN BY: BWS
DATE: APRIL, 2008 CHECKED BY: MJL

DATE: 7/16/2008
TIME: 11:43:31 AM
FILENAME: N:\PROJ\51611\Design\Misc\Sheets\51611-SOQ-03.dgn