F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1230	03-00159-00-PV	LAKE	262	36
STA. 260+00	TO STA. 266+00			
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

CONTRACT: 83828

LEGEND

- DRIVEWAY PAVEMENT REMOVAL
- SIDEWALK REMOVAL
- SPECIAL WASTE AREA
- PAVEMENT REMOVAL
- COMB. CURB AND GUTTER REMOVAL
- HAZARDOUS WASTE AREA

N

*1418 RIM=649.80 42" W. 641.25 36" S. 641.30 30" N. 641.30

*1451 RIM=648.96 36" N. 641.71 36" W. 641.76

*2063 RIM=648.62 6"N. 644.47 8" N. 638.35 8" S. 638.35 10" W.644.27 12"E. 637.04 12"W. 637.04

*1449 RIM=648.80 10" N. 645.75 10" S. 644.90 10" E. 644.65

*1434 RIM=649.64 36"W. 641.69 36"E. 641.84 12" E. 643.14

*2090 RIM=648.38 12"S. 645.43

*2011 RIM=649.50 8" E. 646.70

*2009 RIM=648.13 8" W. 646.55 8"N. 646.45

SEE SHEET NO. 35 MATCHLINE STA. 260+00

MATCHLINE STA. 266+00 SEE SHEET NO. 37

PROPOSED R.O.W.

EXISTING R.O.W.

EXISTING HANDRAIL TO REMAIN

℄ MARTIN LUTHER KING JR. DRIVE

FENCE REMOVAL (STA. 171+84, 38' RT TO 262+91, 33' RT)

SPECIAL WASTE AREA

CULVERT

0 50' 100' — 1"= 20'

EXISTING PROFILE

+1.03% VPI STA. 261+05.99 ELEVATION 650.26 -0.36%

SSD = 577'
gx = -0.35'
K = 144
200.00' V.C.

HIGH POINT STA. 261+54.27 ELEV. 650.00

+0.36% VPI STA. 265+57.37 ELEVATION 648.64 +0.30%

EXISTING ELEVATION

649.05 649.17 | 649.36 649.41 | 649.65 649.62 | 649.91 649.78 | 650.12 649.89 | 650.21 649.97 | 650.23 649.99 | 650.16 649.98 | 650.06 649.92 | 649.90 649.83 | 649.76 649.74 | 649.65 649.65 | 649.53 649.56 | 649.41 649.47 | 649.30 649.38 | 649.22 649.29 | 649.11 649.20 | 648.89 649.11 | 648.90 649.02 | 648.97 648.93 | 649.01 648.84 | 649.01 648.75 | 649.03 648.66 | 649.07 648.69 | 649.09 648.77

260+00 260+50 261+00 261+50 262+00 262+50 263+00 263+50 264+00 264+50 265+00 265+50 266+00

660 655 650 645 640 635 630 625

EXTG. WATER EXTG. 42" STM. EXTG. 36" STM. EXTG. 12" SAN. EXTG. 12" STM. WATER MAIN SAN. INV.=637.9± T/P=638.4± STM INV.=645.31 T/P=646.14 STM INV.=645.5± T/P=646.5± SAN. INV.=637.84± T/P=638.51± WATER SERVICE PROPOSED SAN INV.=640.07 T/P=641.07

CATCH BASIN TYPE B BOX WITH NEENAH R-4342-B GRATE AND CURB INLET

REVISIONS NAME	DATE

Ciorba Group, Inc.
CONSULTING ENGINEERS
5507 North Cumberland Avenue, Suite 402 Chicago, Illinois 60656
Tel. 773.775.4009 Fax 773.775.4014 Email chicago@ciorba.com

CITY OF NORTH CHICAGO
MARTIN LUTHER KING JR. DRIVE IMPROVEMENTS

MARTIN LUTHER KING JR. DRIVE EXISTING CONDITIONS, UTILITIES, AND REMOVAL ITEMS STA. 260+00 TO 266+00

SCALE: 1"=20' DRAWN BY: KMS

DATE: APRIL, 2008 CHECKED BY: MJL

PLAN: SURVEYED, PLOTTED, CHECKED, ALIGNMENT CHECKED, R.O.W. NOTED, CADD FILE NAME, NOTE BOOK, NO.

PROFILE: SURVEYED, PLOTTED, CHECKED, R.O.W. NOTED, STRUCTURE HISTORY NO. ENTRY, NOTE BOOK, NO.

DATE: 6/30/2008
TIME: 10:10:57 AM
FILENAME: N:\PROJ\5161\Design\Removal\5161-REM-11.dgn