

CULVERT AND STORM SEWER SCHEDULE

LOCATION	TYPE	PIPE CULVERT REMOVAL	PIPE CULVERTS, CLASS A, TYPE 1			PRECAST REINFORCED CONCRETE FLARED END SECTIONS			INLETS	TRENCH BACKFILL
			12"	18"	24"	12"	18"	24"	TYPE A, TYPE 8 GRATE	
STATION		FOOT	FOOT	FOOT	FOOT	EACH	EACH	EACH	EACH	CU YD
ITEP BIKE TRAIL										
STA. 20+00.00 LT. 15.24' TO STA. 20+00.00 RT. 12.66'	CULVERT		16.0			2.0				0.7
STA. 29+50.00 LT. 12.66' TO STA. 29+50.00 RT. 13.00'	CULVERT		14.0			2.0				1.6
STA. 30+07.35 RT. 9.29' TO STA. 30+28.65 LT. 7.86'	CULVERT		16.0			2.0				1.8
STA. 31+66.34 RT. 9.84' TO STA. 31+73.10 LT. 12.00'	CULVERT		11.5			2.0				1.0
STA. 36+15.29 LT. 18.49' TO STA. 36+19.38 RT. 17.87'	CULVERT			30.0			2.0			5.4
STA. 36+60.30 RT. 15.80' TO STA. 36+75.70 LT. 15.80'	CULVERT			28.5			2.0			5.7
STA. 42+03.00 LT. 15.01' TO STA. 42+03.00 RT. 21.03'	CULVERT		29.0			1.0		1.0		2.0
STA. 44+51.31 RT. 14.49' TO STA. 44+53.05 LT. 20.97'	CULVERT		29.0			1.0		1.0		1.8
STA. 47+00.00 LT. 13.21' TO STA. 47+00.00 RT. 12.17'	CULVERT				14.0				2.0	2.8
STA. 55+00.00 LT. 13.18' TO STA. 55+00.00 RT. 12.57'	CULVERT				14.0				2.0	10.4
STA. 55+49.40 LT. 25.00'	CULVERT	11								
TOTALS		11	115.5	58.5	28.0	10	4	4	2	33.2
USE		11	116	59	28	10	4	4	2	34

RIPRAP & FILTER FABRIC SCHEDULE

LOCATION	STONE DUMPED RIPRAP, CLASS A4	FILTER FABRIC
STATION	SQ YD	SQ YD
HALL ROAD		
LT STA. 47+00.00	28.6	28.6
RT STA. 47+00.00	148.3	148.3
LT STA. 55+00.00	43.0	43.0
RT STA. 55+00.00	50.8	50.8
TOTALS	270.7	270.7
USE	271	271

FILE NAME = H:\5819\NC_SCH_5819.dgn	USER NAME = _USERDESCR_	DESIGNED - DLD	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>BIKE TRAIL - SCHEDULES</b>	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN - KOJ	REVISED -			06-00025-00-BT	CLINTON	54	6	
		CHECKED -	REVISED -			<b>CONTRACT NO. 97357</b>				
		DATE -	REVISED -			SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT