

SUMMARY OF QUANTITIES (CONTINUED)

		RURAL-UNION COUNTY	
		HBP FUNDING 80% FED. 20% STATE	
		X071-2A	
		SN 091-0022	
CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITIES
48203037	HOT-MIX ASPHALT SHOULDERS, 10"	SQ YD	933
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1
50102400	CONCRETE REMOVAL	CU YD	18.8
50200100	STRUCTURE EXCAVATION	CU YD	97
50300100	FLOOR DRAINS	EACH	4
50300225	CONCRETE STRUCTURES	CU YD	22.1
50300255	CONCRETE SUPERSTRUCTURE	CU YD	68.9
50300260	BRIDGE DECK GROOVING	SQ YD	682.0
50300300	PROTECTIVE COAT	SQ YD	208
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	25,750
50500505	STUD SHEAR CONNECTORS	EACH	1,116
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	17,440
50800515	BAR SPLICERS	EACH	245
51205200	TEMPORARY SHEET PILING	SQ FT	195
51500100	NAME PLATES	EACH	1
52100520	ANCHOR BOLTS, 1"	EACH	24
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	31
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	152
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	388
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4
63200310	GUARDRAIL REMOVAL	FOOT	465
67000400	ENGINEERS FIELD OFFICE, TYPE A	CAL MO	14
67100100	MOBILIZATION	L SUM	1

*Specialty Items

FILE NAME = c:\projects\1902984\1902984ms.dgn	USER NAME = shepardgd	DESIGNED - --- DRAWN - ---	REVISED - --- REVISED - ---	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES (CONTINUED)	F.A.P. RTE. FAP 322	SECTION 12-1, BR	COUNTY UNION	TOTAL SHEETS 48	SHEET NO. 5
PLOT SCALE = 50,0000 1" = IN.		CHECKED - ---	REVISED - ---	SCALE: _____ SHEET NO. 5 OF 48 SHEETS STA. _____ TO STA. _____		FED. ROAD DIST. NO. _____ ILLINOIS FED. AID PROJECT		CONTRACT NO. 98886		
PLOT DATE = 7/1/2008		DATE - _____	REVISED - ---							