

PAVEMENT AND RESURFACING SCHEDULE

LOCATION STATION TO STATION	HOT-MIX ASPHALT SURFACE COURSE TON	PRIME COAT		HOT-MIX ASPHALT SHOULDERS, 10" SQ YD	HOT-MIX ASPHALT SURFACE REMOVAL 1 1/2" SQ YD	PAVED SHOULDER REMOVAL SQ YD	TEMPORARY RAMP SQ YD	PAVEMENT REMOVAL SQ YD
		BITUMINOUS MATERIALS GAL	AGGREGATE TON					
FAP RT. 322(US 51)								
798+50 TO 799+40 RT						40.0		
799+40 TO 800+00 RT						57.0		
800+00 TO 800+84 RT						122.3		
800+84 TO 801+20 RT						14.0		
801+62 TO 802+36 RT						34.1		
802+36 TO 802+76 RT						63.6		
802+76 TO 803+29 RT						57.4		
803+29 TO 803+58 RT						14.5		
799+70 TO 800+00 LT						14.3		
800+00 TO 800+50 LT						52.5		
800+50 TO 800+90 LT						59.6		
800+90 TO 801+57 LT						26.1		
801+90 TO 802+36 LT						17.9		
802+36 TO 802+60 LT						33.3		
802+60 TO 803+00 LT						58.9		
803+00 TO 803+96 LT						96.0		
803+96 TO 804+50 LT						24.0		
799+70 TO 799+90 LT				20.0				
799+90 TO 800+50 LT				83.3				
800+50 TO 800+84 LT				41.6				
• 800+84 TO 801+57 LT				20.3				247.6
801+98 TO 802+36 LT				10.6				
802+36 TO 803+00 LT	14.3	22.4	0.3	78.2	170.7			
803+00 TO 804+30 LT	29.1	47.5	0.5	180.6	346.7			
804+30 TO 804+50 LT	4.5	6.6	0.1	20.0	53.3		13.5	
798+50 TO 798+73 RT	5.2	7.6	0.1	23.0	61.3		13.5	
798+73 TO 799+43 RT	15.7	25.6	0.3	97.2	186.7			
799+43 TO 800+84 RT	32.9	50.8	0.6	172.3	376.0			
800+84 TO 801+21 RT				10.3				
• 801+62 TO 802+36 RT				20.6				247.6
802+36 TO 802+67 RT				37.9				
802+67 TO 803+34 RT				93.1				
803+34 TO 803+58 RT				24.0				
TOTALS	102	160	2	933	1195	785	27	495

*PAVEMENT REMOVAL LIMITS ARE STATION 800+84.0 TO 801+39.7 AND STATION 801+80.3 TO 802+36.0

FILE NAME = c:\projects\922984\922924.mxd	USER NAME = shepardgd	DESIGNED - ---	REVISED - ---	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PAVEMENT AND RESURFACING SCHEDULE	F.A.P. RTE. FAP 322	SECTION 12-1, BR	COUNTY UNION	TOTAL SHEETS 48	SHEET NO. 9
		DRAWN - ---	REVISED - ---							
		CHECKED - ---	REVISED - ---							
		DATE - ---	REVISED - ---							
					SCALE: _____	SHEET NO. 9 OF 48 SHEETS	STA. _____	TO STA. _____	FED. ROAD DIST. NO. _____ ILLINOIS FED. AID PROJECT	
									CONTRACT NO. 98886	