

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
782	114B-2	GALLATIN	62	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

# SUMMARY OF QUANTITIES

		RURAL-GALLATIN COUNTY HBP FUNDING 80% FED. 20% STATE X071-2A SN 030-0024	
CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITIES
20100500	TREE REMOVAL, ACRES	ACRE	1.75
20200100	EARTH EXCAVATION	CU YD	2,423
20300100	CHANNEL EXCAVATION	CU YD	1,719
20400100	BORROW EXCAVATION	CU YD	9,716
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	258
25000200	SEEDING, CLASS 2	ACRE	1.50
25000350	SEEDING, CLASS 7	ACRE	2.50
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	226
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	135
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	135
25000700	AGRICULTURAL GROUND LIMESTONE	TON	3.0
25100115	MULCH, METHOD 2	ACRE	2.75
25100630	EROSION CONTROL BLANKET	SQ YD	6,364
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	453
28000300	TEMPORARY DITCH CHECKS	EACH	5
28000400	PERIMETER EROSION BARRIER	FOOT	2,129
28100109	STONE RIPRAP, CLASS A5	SQ YD	2,196
28200200	FILTER FABRIC	SQ YD	2,196
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	35
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	467
40600300	AGGREGATE (PRIME COAT)	TON	3
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	201
40600990	TEMPORARY RAMP	SQ YD	46
40603090	HOT MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	719
40603320	HOT MIX ASPHALT SURFACE COURSE, MIX "C", N90	TON	160
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	222
42001300	PROTECTIVE COAT	SQ YD	266.7