

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
782	114B-2	GALLATIN	62	5
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

		RURAL-GALLATIN COUNTY HBP FUNDING 80% FED. 20% STATE X071-2A SN 030-0024	
CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITIES
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	44.5
44000100	PAVEMENT REMOVAL	SQ YD	1,353
44004250	PAVED SHOULDER REMOVAL	SQ YD	124
48203100	HOT-MIX ASPHALT SHOULDERS	TON	307
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1
50200100	STRUCTURE EXCAVATION	CU YD	240
50300100	FLOOR DRAINS	EACH	14
50300225	CONCRETE STRUCTURES	CU YD	44.4
50300255	CONCRETE SUPERSTRUCTURE	CU YD	187.6
50300260	BRIDGE DECK GROOVING	SQ YD	706.5
50300280	CONCRETE ENCASEMENT	CU YD	4.2
50300300	PROTECTIVE COAT	SQ YD	580
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1
50500505	STUD SHEAR CONNECTORS	EACH	1,350
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	44,440
50800515	BAR SPLICERS	EACH	64
51201700	FURNISHING STEEL PILES HP12X74	FOOT	674
51202305	DRIVING PILES	FOOT	674
51203700	TEST PILE STEEL HP12X74	EACH	1
51300105	TEMPORARY BRIDGE COMPLETE	EACH	1
51500100	NAME PLATES	EACH	1
52100520	ANCHOR BOLTS, 1"	EACH	24
542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	36
54215553	METAL END SECTIONS 18"	EACH	2
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	108
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	168