

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
782	114B-2	GALLATIN	62	10
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SHOULDER SCHEDULE

LOCATION STATION TO STATION			LENGTH (FOR INFORMATION ONLY) FEET	HOT-MIX ASPHALT SHOULDERS TON	PRIME COAT BITUMINOUS MATERIALS GAL	PAVED SHOULDER REMOVAL SQ YD	GENERAL COMMENTS
FAP RT. 782 (IL 1)							
LT 799+03	TO	LT 800+75	172.0	10.9	7		CAP DETOUR PAVEMENT
LT 800+75	TO	LT 801+17	42.0	8.0	9		CORE AGGREGATE, NEW SHOULDER
LT 801+17	TO	LT 801+41	24.0	6.7	7		CORE AGGREGATE, NEW SHOULDER
LT 801+41	TO	LT 801+56	15.0	5.5	4		CORE AGGREGATE, NEW SHOULDER
LT 801+56	TO	LT 802+58	102.0	28.5	8		CAP EXISTING SHOULDER
LT 802+58	TO	LT 802+93	35.0	8.0	6	11.3	REMOVE SHOULDER, PLACE NEW
LT 802+93	TO	LT 803+00	7.0			2.3	REMOVE SHOULDER
NE QUAD							
LT 804+21	TO	LT 804+27	6.5			2.1	REMOVE SHOULDER
LT 804+27	TO	LT 804+62	35.0	8.0	6	13.6	REMOVE SHOULDER, PLACE NEW
LT 804+62	TO	LT 805+60	98.0	28.5	8		CAP EXISTING SHOULDER
LT 805+60	TO	LT 806+50	90.0	24.5	7		CAP EXISTING SHOULDER
LT 806+50	TO	LT 808+18	168.0	25.4	10	65.3	CAP DETOUR PAVEMENT
SE QUAD							
RT 799+45	TO	RT 800+16	71.0	13.5	11		CORE AGGREGATE, NEW SHOULDER
RT 800+16	TO	RT 800+42	26.0	7.2	5		CORE AGGREGATE, NEW SHOULDER
RT 800+42	TO	RT 801+56	114.0	41.6	31		CORE AGGREGATE, NEW SHOULDER
RT 801+56	TO	RT 802+58	102.0	29.6	8		CAP EXISTING SHOULDER
RT 802+58	TO	RT 802+93	35.0	8.0	6	11.3	REMOVE SHOULDER, PLACE NEW
RT 802+93	TO	RT 803+00	7.0			2.3	REMOVE SHOULDER
NW QUAD							
RT 804+21	TO	RT 804+27	6.5			2.1	REMOVE SHOULDER
RT 804+27	TO	RT 804+62	35.0	8.0	6	13.6	REMOVE SHOULDER, PLACE NEW
RT 804+62	TO	RT 807+75	313.0	45.2	18		CAP EXISTING SHOULDER
SW QUAD							
TOTALS				307	156	124	

PAVEMENT SCHEDULE

LOCATION STATION TO STATION			LENGTH (FOR INFORMATION ONLY) FEET	AREA (FOR INFORMATION ONLY) SQ FEET	HOT-MIX ASPHALT BINDER COURSE TON	HOT-MIX ASPHALT SURFACE COURSE TON	PRIME COAT		PAVEMENT REMOVAL SQ YD	HOT-MIX ASPHALT PAVEMENT REMOVAL BUTT-JOINT SQ YD	TEMPORARY RAMP SQ YD
							BITUMINOUS MATERIALS GAL	AGGREGATE TON			
DETOUR ROAD											
799+03	TO	799+72	72.2	252.0	17.6		2				
799+72	TO	800+75	104.2	1020.7	66.2		9		75.5		
800+75	TO	802+85	210.2	2983.5	196.6		27		331.5		
802+85	TO	804+40									
804+40	TO	806+36	196.2	2786.3	183.6		25		309.6		
806+36	TO	807+52	116.7	1293.1	83.5		11		80.0		
807+52	TO	808+18	68.2	239.8	16.7		2				
FAP RT. 782 (IL 1)											
799+45	TO	800+00	55.0			16.6	21	0.3		72.2	20.2
800+00	TO	802+58	258.0		71.9	64.0	97	1.2			
802+58	TO	803+34	76.0						278.7		
803+34	TO	803+87	52.5								
803+87	TO	804+62	75.5						276.8		
804+62	TO	807+20	258.0		82.6	63.8	97	1.2			
807+20	TO	807+75	55.0			15.8	21	0.3		128.3	25.7
TOTALS					719	160	311	3	1353	201	46