

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
782	114B-2	GALLATIN	62	11
STA.		TO STA.		
FED. ROAD DIST. NO. _		ILLINOIS	FED. AID PROJECT	

# TREE REMOVAL SCHEDULE

LOCATION STATION AND OFFSETS FROM CENTERLINE	TREE REMOVAL
	ACRES
802+75, 20' RT AND 76' RT	
805+50, 20' RT AND 75' RT	0.35
806+50, 20' RT AND 90' RT	0.14
807+75, 20' RT AND 37' RT	0.18
808+00, 20' RT AND 37' RT	0.03
800+00, 20' LT AND 40' LT	
801+00, 20' LT AND 55' LT	0.06
802+00, 20' LT AND 67' LT	0.09
802+50, 20' LT AND 86' LT	0.06
805+00, 20' LT AND 94' LT	0.40
806+50, 20' LT AND 86' LT	0.24
807+00, 20' LT AND 55' LT	0.06
808+00, 20' LT AND 47' LT	0.07
TOTALS	1.75

# PAVEMENT MARKING SCHEDULE

LOCATION STATION TO STATION	PAVEMENT MARKING REMOVAL SQ FT	TEMPORARY PAVEMENT MARKING LINE - 4"		PAINT PAVEMENT MARKING - LINE 4"		SHORT TERM PAVEMENT MARKING FOOT	WORK ZONE PAVEMENT MARKING REMOVAL SQ FT	RAISED REFLECTIVE PAVEMENT MARKER EACH	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL EACH
		WHITE FOOT	YELLOW FOOT	WHITE FOOT	YELLOW FOOT				
DETOUR									
799+00 TO 799+72	24.0	144.0							
799+72 TO 800+75	34.3	206.0							
800+75 TO 802+85		420.0							
802+85 TO 804+40		310.0							
804+40 TO 806+36		392.0							
806+36 TO 807+52	38.5	231.0							
807+52 TO 808+20	22.7	136.0							
FAP RT. 782 ( IL 1 )									
799+03 TO 808+18	375.0	1830.0	228.8	1830.0	228.8	156.4	686.2	13.0	13.0
TOTALS	494	3669	229	1830	229	156	686	13	13
		3898		2059					