

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
782	114B-2	GALLATIN	62	12
STA.		TO STA.		
FED. ROAD DIST. NO. _		ILLINOIS	FED. AID PROJECT	

SEEDING AND EROSION CONTROL SCHEDULE

LOCATION STATION TO STATION	SEEDING CLASS 2 ACRE	SEEDING CLASS 7 (TEMPORARY) ACRE	NITROGEN FERTILIZER NUTRIENTS		PHOSPHORUS FERTILIZER NUTRIENTS POUND	POTASSIUM FERTILIZER NUTRIENTS POUND	AGRICULTURAL GROUND LIMESTONE TON	EROSION CONTROL BLANKET SQ YD	MULCH METHOD 2 FOR CLASS 2 ACRE	MULCH METHOD 2 FOR CLASS 7 ACRE	TEMPORARY EROSION CONTROL SEEDING POUND
			CLASS 2 POUND	CLASS 7 POUND							
STAGE 1 (DETOUR ROAD)		0.76		30.5				3613.0		0.02	153
STAGE 2 (PRE-FINAL GRADING)	0.65	0.65	58.5	26.0	58.5	58.5	1.3	1042.6	0.43	0.65	130
STAGE 3 (FINAL GRADING)	0.85	0.85	76.5	34.0	76.5	76.5	1.7	1708.0	0.50	0.85	170
TOTALS	1.50	2.50	135	91	135	135	3.0	6364	1.00	1.75	453
			226						2.75		

RIGHT OF WAY SCHEDULE

LOCATION STATION	OFFSET FROM CL FEET	ROW MARKERS EACH
FAP RT. 782 (IL 1)		
800+00	40 RT	1
800+00	60 RT	1
800+00	40 LT	1
800+00	110 LT	1
801+00	60 RT	1
808+00	60 LT	1
808+00	110 LT	1
TOTALS		7