

SUMMARY OF QUANTITIES			URBAN		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE 0005					
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	40	40					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	586	586					
25200110	SODDING, SALT TOLERANT	SO YD	586	586					
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SO YD	200	200					
40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUND	82791	82791					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	224	224					
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	4324	4324					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	236	236					
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SO YD	2345	2345					
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	23	23					
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	12826	12826					

SUMMARY OF QUANTITIES			URBAN		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE 0005					
42001300	PROTECTIVE COAT	SO YD	1829	1829					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	3898	3898					
42400800	DETECTABLE WARNINGS	SO FT	860	860					
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	5582	5582					
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	200	200					
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SO FT	63364	63364					
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	2800	2800					
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SO YD	500	500					
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SO YD	750	750					
48101200	AGGREGATE SHOULDERS, TYPE B	TON	16	16					
60250200	CATCH BASINS TO BE ADJUSTED	EACH	103	103					
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	3	3					
60255500	MANHOLES TO BE ADJUSTED	EACH	29	29					
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	4	4					
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	20	20					

FILE NAME =	USER NAME = pml/ped	DESIGNED -	REVISED -
CLIP.../work/pml/ped/pml/ped/02307/PHOTO/01-01-01.dwg		DRAWN -	REVISED -
PLOT SCALE = 100.0000' / 1"		CHECKED -	REVISED -
PLOT DATE = 7/17/2014		DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

IL 58 (WEST OF POTTER RD. TO LINCOLN ST.)  
SUMMARY OF QUANTITIES

SCALE:	SHEET NO. OF SHEETS	STA. TO STA.
--------	---------------------	--------------

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
339	584Y-RS-2	COOK	37	3
CONTRACT NO. 60M09			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT	