


CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE						
				90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	
				ROADWAY	S.N. 016-1510	S.N. 016-1512	SAFETY	SIGN STRUCTURES	DRAINAGE	
				0005 URBAN	0014 URBAN	0014 URBAN	0021 URBAN	0040 URBAN	0044 URBAN	
X7030025	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH 	FOOT	2398	2398						
<del>X8040310</del>	<del>ELECTRIC SERVICE DISCONNECT</del>	<del>EACH</del>	<del>2</del>				<del>2</del>			
X8710027	FIBER OPTIC CABLE, 4 FIBERS, SINGLE MODE	FOOT	300				300			
X8710030	FIBER OPTIC CABLE 48 FIBERS, SINGLE MODE	FOOT	5000				5000			
X8730249	ELECTRIC CABLE IN CONDUIT, NO. 19 6/C	FOOT	750				750			
X8730312	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO.18 4/C, TWISTED, SHIELDED	FOOT	1100				1100			
X8850102	INDUCTION LOOP	FOOT	40				40			
XX006821	CONCRETE TRUCK WASHOUT	L SUM	1				1			
X0328502	CLOSED CIRCUIT TELEVISION CAMERA STRUCTURE, GALVANIZED STEEL, 50' MOUNTING HEIGHT	EACH	2				2			
X0325500	STAINLESS STEEL JUNCTION BOX TYPE "J", INSTALL ONLY	EACH	4				4			
87000785	ELECTRIC CABLE ASSEMBLY IN CONDUIT, 600V(XLP-TYPE TC) 2/C NO. 2 AND NO.6 GRND	FOOT	1500				1500			
X0327905	ELECTRIC CABLE NO. 19, 50 PAIR	FOOT	5500				5500			
<del>X0329905</del>	<del>TEMPORARY WOOD POLE, 50 FT, CLASS 4</del>	<del>L SUM</del>	<del>1</del>				<del>1</del>			

• SPECIALTY ITEM

*Rev. 9-11-14*

*Rev.*

FILE NAME -	DESIGNED -	REVISED -
\\NGenerat\N0160W77\shd-500-12.dgn	DRAWN -	REVISED -
USER NAME - jmejkvst	CHECKED -	REVISED -
PLOT DATE - 6/23/2014	DATE - 6/23/2014	REVISED -



STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N.T.S. SHEET 10 OF 10 SHEETS STA. TO STA.

F.A.P. RIE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
373	0707-608 & 611HB-B	COOK	177	135
CONTRACT NO. 60W77			ILLINOIS FED. AID PROJECT	