

EARTHWORK ITEMS

			VOLUME (CU YD)				
Station To Station	Length		Earth Excavation (Suitable Cut)	Earth Excavation (15% S.F.) Used for Embankment	Embankment (Suitable Fill) (Furnished Excavation)	Earthwork Balance (+) - Wastage / (-) - Shortage	Topsoil Excavation And Placement
RAMP B (I-55 NB ON-RAMP)							
6001+35	6001+50	15.0	0	0	89	-89	17
6001+50	6002+00	50.0	0	0	689	-689	126
6002+00	6002+50	50.0	0	0	739	-739	132
6002+50	6003+00	50.0	0	0	641	-641	124
6003+00	6003+50	50.0	0	0	593	-593	120
6003+50	6004+00	50.0	0	0	596	-596	122
6004+00	6004+50	50.0	0	0	610	-610	124
6004+50	6005+00	50.0	0	0	655	-655	127
6005+00	6005+50	50.0	0	0	684	-684	128
6005+50	6006+00	50.0	0	0	785	-785	130
6006+00	6006+35	35.0	0	0	310	-310	46
6006+35							
SUB-TOTAL ==>>			0	0	6390	-6390	1195
RAMP D (I-55 SB ON-RAMP)							
9001+65	9002+00	35.0	0	0	164	-164	42
9002+00	9002+50	50.0	0	0	661	-661	133
9002+50	9003+00	50.0	0	0	781	-781	134
9003+00	9003+50	50.0	0	0	635	-635	120
9003+50	9004+00	50.0	0	0	526	-526	114
9004+00	9004+50	50.0	0	0	503	-503	112
9004+50	9005+00	50.0	0	0	513	-513	111
9005+00	9005+50	50.0	0	0	508	-508	109
9005+50	9005+70	20.0	0	0	101	-101	21
9005+70							
SUB-TOTAL ==>>			0	0	4393	-4393	897
TOTAL BY PAY-ITEM ==>>			0	0	10,782	-10,782	2,092
USE ==>>			0	0	10,790	-10,790	2,100

FILE NAME : D:\60Y53-shr-02-Earthwork_Schedule_01.dgn

USER NAME = llugo	DESIGNED LL	REVISED -
	DRAWN KES	REVISED -
PLOT SCALE = 1:2,000	CHECKED PJO	REVISED -
PLOT DATE = 7/16/2014	DATE 7/16/2014	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES		
EARTHWORK ITEMS		
SCALE: NONE	SHEET NO. 1 OF 1 SHEETS	STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	(99-1HB-1)A	WILL	33	8
CONTRACT NO. 60Y53			ILLINOIS FED. AID PROJECT	