

CONSTRUCTION NOTES	
1.	THE LOCATION OF ALL UTILITIES AND PRIVATELY OWNED FACILITIES SHALL BE FIELD VERIFIED BY THE CONTRACTOR PRIOR TO EXCAVATION.
2.	THE CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING EXISTING IDOT ELECTRICAL FACILITIES. THE CONTRACTOR SHALL ALSO BE LIABLE FOR ANY DAMAGE TO IDOT FACILITIES RESULTING FROM INACCURATE LOCATING.
3.	NO WORK OF ANY KIND IS TO BE PERFORMED BY THE CONTRACTOR, UNLESS A WORK ORDER AUTHORIZING THE WORK HAS BEEN ISSUED BY THE ENGINEER.
4.	NO SUBCONTRACTORS MAY BE UTILIZED WITHOUT APPROVAL FROM THE DEPARTMENT.
5.	WHEN THE DEPARTMENT AUTHORIZES THE USE OF A SUBCONTRACTOR IN THE EXECUTION OF A WORK ORDER, THE DEPARTMENT WILL PAY THE CONTRACTOR THE ACTUAL AMOUNT OF THE SUBCONTRACTOR INVOICE PLUS A FIVE PERCENT MAXIMUM MARK UP FOR PROCESSING.
6.	THE CONTRACTOR SHALL RECEIVE THE ACTUAL COST FOR PARTS AND MATERIALS SUPPLIED (INCLUDING TRANSPORTATION CHARGES PAID BY THE CONTRACTOR) TO WHICH COST A MAXIMUM OF 15 PERCENT WILL BE ADDED.
7.	ALL OTHER INCIDENTAL EQUIPMENT AND TOOLS SHALL BE PROVIDED BY CONTRACTOR AT PRICES ESTABLISHED IN THE EQUIPMENT WATCH RENTAL RATE BLUE BOOK WHICH CAN BE OBTAINED AT <a href="http://www.equipmentwatch.com">HTTP://WWW.EQUIPMENTWATCH.COM</a> .
8.	EQUIPMENT AND TOOLS THAT ARE NOT LISTED IN THE EQUIPMENT WATCH RENTAL RATE BLUE BOOK SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT, AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.
9.	TRAFFIC CONTROL AND PROTECTION WILL NOT BE PAID FOR SEPARATELY BUT SHALL BE INCLUDED IN THE APPLICABLE PAY ITEMS LISTED IN THIS CONTRACT. THE DEPARTMENT WILL PAY THE CONTRACTOR FOR THE ACTUAL TIME AND MATERIALS REQUIRED TO INSTALL AND REMOVE TRAFFIC CONTROL STANDARDS.
10.	WITH THE APPROVAL OF THE DEPARTMENT, THE CONTRACTOR MAY UTILIZE SUBCONTRACTORS TO PROVIDE INTERSTATE LANE CLOSURES AND OTHER COMPLEX TRAFFIC CONTROL INSTALLATIONS. THE DEPARTMENT WILL REIMBURSE THE CONTRACTOR FOR THE ACTUAL AMOUNT OF THE SUBCONTRACTOR INVOICE PLUS A FIVE PERCENT MAXIMUM MARK-UP TO COVER PROCESSING.

HIGHWAY STANDARDS	
STANDARD	APPLICATION
000001 - 01	STANDARD SYMBOLS, ABBREVIATIONS, AND PATTERNS
001006	DECIMAL OF AN INCH AND OF A FOOT
701001 - 02	OFF-ROAD OPERATIONS, 2L, 2W, MORE THAN 4.5 M (15') AWAY
701006 - 05	OFF-ROAD OPERATIONS, 2L, 2W, 4.5 M (15') TO 600 MM (24") FROM PAVEMENT EDGE
701101 - 04	OFF-ROAD OPERATIONS, MULTILANE, 4.5 M (15') TO 600 MM (24") FROM PAVEMENT EDGE
701106 - 02	OFF-ROAD OPERATIONS, MULTILANE, MORE THAN 4.5 (15') AWAY
701201 - 04	LANE CLOSURE, 2L, 2W, DAY ONLY, FOR SPEEDS, ≥ 45 MPH
701206 - 03	LANE CLOSURE, 2L, 2W, NIGHT ONLY, FOR SPEEDS, ≥ 45 MPH
701301 - 04	LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS
701306 - 03	LANE CLOSURE, 2L, 2W, SLOW MOVING OPERATIONS DAY ONLY, FOR SPEEDS ≥ 45 MPH
701311 - 03	LANE CLOSURE, 2L, 2W, MOVING OPERATIONS - DAY ONLY
701400 - 07	APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY
701401 - 08	LANE CLOSURE, FREEWAY/EXPRESSWAY
701406 - 08	LANE CLOSURE, FREEWAY/EXPRESSWAY, DAY OPERATIONS ONLY
701411 - 08	LANE CLOSURE, MULTILANE AT ENTRANCE OR EXIT RAMP FOR SPEEDS ≥ 45 MPH
701421 - 06	LANE CLOSURE, MULTILANE, DAY OPERATIONS ONLY, FOR SPEEDS ≥ 45 MPH TO 55 MPH
701422 - 06	LANE CLOSURE, MULTILANE, FOR SPEEDS ≥ 45 MPH TO 55 MPH
701426 - 06	LANE CLOSURE, MULTILANE, INTERMITTENT OR MOVING OPERATIONS FOR SPEEDS ≤ 40 MPH
701427 - 02	LANE CLOSURE, MULTILANE, INTERMITTENT OR MOVING OPERATIONS FOR SPEEDS ≥ 45 MPH
701431 - 09	LANE CLOSURE, MULTILANE, UNDIVIDED WITH CROSSOVER, FOR SPEEDS ≥ 45 MPH TO 55 MPH
701446 - 05	TWO LANE CLOSURE, FREEWAY/EXPRESSWAY
701451 - 02	RAMP CLOSURE, FREEWAY / EXPRESSWAY
701456 - 03	PARTIAL EXIT RAMP CLOSURE, FREEWAY / EXPRESSWAY
701501 - 06	URBAN LANE CLOSURE, 2L, 2W, UNDIVIDED
701502 - 06	URBAN LANE CLOSURE, 2L, 2W, BI-DIRECTIONAL LEFT TURN LANE
701601 - 09	URBAN LANE CLOSURE, MULTILANE, 1W OR 2W WITH NON TRAVERSABLE MEDIAN
701602 - 07	URBAN LANE CLOSURE, MULTILANE, 2 WAY WITH BI-DIRECTIONAL LEFT TURN LANE
701606 - 09	URBAN LANE CLOSURE, MULTILANE, 2 WAY WITH MOUNTABLE MEDIAN
701701 - 09	URBAN LANE CLOSURE, MULTILANE INTERSECTION
701801 - 05	SIDEWALK, CORNER OR CROSSWALK CLOSURE
701901 - 03	TRAFFIC CONTROL DEVICES

THERE ARE NO COMMITMENTS IN CONJUNCTION WITH THIS PROJECT.