

SCHEDULE OF QUANTITIES

I-74 EASTBOUND CLASS B 15" PATCHES												
COUNTY	URBAN/ RURAL	STATION	MILEPOST	DIRECTION	LANE	LENGTH (FT)	WIDTH (FT)	44201037 TYPE IV 15.0" (SQ YD)	44201299 DOWEL BARS 1 1/2" (EACH)	44213200 SAW CUTS (FT)	44213204 TIE BARS 3/4" (EACH)	44213100 PAVEMENT FABRIC (SQ YD)
VERMILION	RURAL	1318+16.88	202.796	WB	DL	40	12	53.3	40	116.0	20	53.3
SUB-TOTALS =								53.3	40.0	116.0	20.0	53.3
TOTALS =								53.3	40.0	116.0	20.0	53.3
VERMILION CO. I-74 RURAL TOTALS =								54.0	40.0	116.0	20.0	54.0
USE =								54.0	40.0	116.0	20.0	54.0

I-74 EASTBOUND CLASS B 17" PATCHES												
COUNTY	URBAN/ RURAL	STATION	MILEPOST	DIRECTION	LANE	LENGTH (FT)	WIDTH (FT)	44201055 TYPE II 17.0" (SQ YD)	44201057 TYPE III 17.0" (SQ YD)	44201299 DOWEL BARS 1 1/2" (EACH)	44213200 SAW CUTS (FT)	44213100 PAVEMENT FABRIC (SQ YD)
VERMILION	URBAN	1882+60.08	213.486	EB	DL	6	12	8.0	0.0	20	48.0	0.0
VERMILION	URBAN	1882+60.08	213.486	EB	PL	6	12	8.0	0.0	20	48.0	0.0
VERMILION	URBAN	1885+76.88	213.546	EB	DL	12	12	0.0	16.0	20	60.0	16.0
VERMILION	URBAN	1886+56.08	213.561	EB	PL	6	12	8.0	0.0	20	48.0	0.0
SUB-TOTALS =								24.0	16.0	80.0	204.0	16.0
TOTALS =								24.0	16.0	80.0	204.0	16.0
VERMILION CO. I-74 URBAN TOTALS =								24.0	16.0	80.0	204.0	16.0
USE =								24.0	16.0	80.0	204.0	16.0

FILE NAME =	USER NAME = gorees	DESIGNED -	REVISED -
ct:\pw\work\p1dot\gorees\d0400102\0570A	l-sh-t-cover-soq-schedules.dgn	DRAWN -	REVISED -
\$MODELNAME\$	PLOT SCALE = 40.0000' / in.	CHECKED -	REVISED -
	PLOT DATE = 6/26/2014	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES			
SCALE:	SHEET 4	OF 4 SHEETS	STA. TO STA.

*VARIOUS		**CHAMPAIGN, DOUGLAS, & VERMILION		
F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	D5 CM PATCHING 2015-2	**	32	31
CONTRACT NO. 70A81			ILLINOIS FED. AID PROJECT	