

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				100% STATE	
				ROADWAY 0004 S.N.	BRIDGE 0011 S.N.
48203100	HOT-MIX ASPHALT SHOULDERS	TON	116	116	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
50104400	CONCRETE HEADWALL REMOVAL	EACH	2	2	
50104650	SLOPE WALL REMOVAL	SQ YD	580	580	
50105220	PIPE CULVERT REMOVAL	FOOT	73	73	
50200100	STRUCTURE EXCAVATION	CU YD	354		354
50300225	CONCRETE STRUCTURES	CU YD	114		114
50300255	CONCRETE SUPERSTRUCTURE	CU YD	316.6		316.6
50300260	BRIDGE DECK GROOVING	SQ YD	553		553
50300300	PROTECTIVE COAT	SQ YD	690		690
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1
50500505	STUD SHEAR CONNECTORS	EACH	990		990
50800105	REINFORCEMENT BARS	POUND	2900	2900	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	77910		77,910
50800515	BAR SPLICERS	EACH	437		437

14

FILE NAME : I:\DB07404-IL104 Over Brower Creek\CADD	USER NAME : jowley	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -		745	1088-3	PIKE	65	5				
		CHECKED -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.				CONTRACT NO. 72861				
		DATE -	REVISED -		FED. ROAD DIST. NO. 6 ILLINOIS FED. AID PROJECT								