

SUMMARY OF QUANTITIES				CONSTRUCTION CODE		
				100% STATE	100% STATE	100% STATE
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	ROADWAY	ROADWAY
				0005	0021	0004
				6-00706-0000	6-00706-0000	6-00743-0000
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	50	50		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	821	821		
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SO YD	874	874		
40600990	TEMPORARY RAMP	SO YD	144	144		
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	663	663		
40603087	HOT-MIX ASPHALT BINDER COURSE, IL-19.0 FG, N70	TON	6582	6445		137
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	442	442		
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	4388	4296		92
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	83	83		
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	43	43		
44000500	COMBINATION CURB AND CUTTER REMOVAL	FOOT	3057	3057		
44003100	MEDIAN REMOVAL	SO FT	13778	13778		
44004250	PAVED SHOULDER REMOVAL	SO YD	1566			1566
44200525	CLASS A PATCHES, TYPE I, 8 INCH	SO YD	16	16		

FILE NAME =	USER NAME = sparkag	DESIGNED - JWC	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
\\p-work\p-dot\sparkag\0330002\067\F98-sht-500.dgn	PLOT SCALE = 100.0000' / 1" =	DRAWN - JWC	REVISED -					562	(1-2) RS-1,N	SANGAMON	89	4
Default	PLOT DATE = Jul-14-2014 01:54:59PM	CHECKED - JWC	REVISED -		SCALE:	SHEET	OF	SHEETS	STA.	TO STA.	CONTRACT NO. 72F96	
		DATE -	REVISED -								ILLINOIS FED. AID PROJECT	