## INDEX OF SHEETS

- 1. COVER SHEET
- 2. GENERAL NOTES
- 3. SUMMARY OF QUANTITIES
- 4. SCHEDULE OF QUANTITIES 5.-9. PLAN SHEETS

## HIGHWAY STANDARDS

000001-06

701001-02

701006-05

701901-03

## GENERAL NOTES

- ANY REFERENCE TO A STANDARD IN THESE PLANS SHALL BE INTERPRETED TO MEAN THE EDITION AS INDICATED BY THE SUBNUMBER LISTED ON THE INDEX OF SHEETS OR THE COPY OF THE STANDARD INCLUDED IN THESE PLANS.
- 2. THE LOCATIONS OF THE BURIED AND ABOVE GROUND UTILITIES SHOWN IN THE PLANS ARE APPROXIMATE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING UTILITY PROPERTY FROM CONSTRUCTION OPERATIONS AS OUTLINED IN ARTICLE 107.26 OF THE STANDARD SPECIFICATIONS. THE J.U.L.I.E. NUMBER IS (800) 892-0123. A MINIMUM OF FORTY-EIGHT HOURS ADVANCED NOTICE IS REQUIRED PRIOR TO PROCEEDING WITH ANY EXCAVATION WORK ON THE PROJECT.
- 3. WHERE SECTION OR SUBSECTION MONUMENTS ARE ENCOUNTERED, THE ENGINEER SHALL BE NOTIFIED BEFORE SUCH MONUMENTS ARE REMOVED. THE CONTRACTOR SHALL PROTECT AND CAREFULLY PRESERVE ALL MONUMENTS UNTIL AN AUTHORIZED SURVEYOR OR AGENT HAS WITNESSED OR OTHERWISE REFERENCED THEIR LOCATION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR HAVING AN AUTHORIZED SURVEYOR RE-ESTABLISH ANY SECTION OR SUBSECTION MONUMENTS DESTROYED BY HIS OPERATIONS.
- 4. UNLESS NOTED OTHERWISE, STATIONS AND OFFSETS REFER TO CENTERLINE OF PROJECT,

SCALE:

SHEET

- 5. DISTRICT 6 SURVEYS WILL LAY OUT THE TREE REMOVAL LIMITS. CONTACT BRAD DUZAN AT 217-782-8707 THREE WEEKS PRIOR TO REMOVING THE TREES.
- 6. THE ILLINOIS DEPARTMENT OF NATURAL RESOURCES HAS ISSUED TREE REMOVAL RESTRICTIONS DUE TO THE FEDERALLY LISTED SPECIES HABITAT (INDIANA GREY BAT) AND HAS RECEIVED CONCURRENCE FROM THE US FISH & WILDLIFE TO IMPLEMENT RESTRICTIONS ON THIS PROJECT. NO TREE SHALL BE REMOVED ON THIS PROJECT FROM APRIL IST TO SEPTEMBER IST ON ANY GIVEN YEAR.

## COMMITMENTS

A COMMITMENT WAS MADE WITH THE MCGEE CREEK LEVEE DRAINAGE DISTRICT THAT 3" OF AGGREGATE SURFACE WOULD BE PLACED ON THE ENTRANCE THAT THE TREE REMOVAL CONTRACTOR USES FOR GAINING ACCESS TO THE MEREDOSIA TERMINAL PROPERTY TO REMOVE THE TREES.

EXAMINED 7/1	20 14
OPERATIONS ENGINEER	seecolory
examined June 30	20 14
PROJECT IMPLEMENTATION EN	•
EXAMINED July 3	
Self P. Mrs	20 /4
PROGRAM DEVELOPMENT ENGI	NEER

DISTRICT SIX

1	FILE NAME :	USER NAME + coxte	DESIGNED -	***	REVISED	-
1	ci\pw_work\p=idoi\coxis\d040(567\0672H2	Braht-gennote.dgn	DRAWN -		REVISED	-
ł		PLOT SCALE * 100,0000 1/ in.	CHECKED -	~~~~~	REVISED	* ~->
L	O=Foult	PLOT DATE = Jul-02-2014 04:22:06PM	DATE -	~	REVISED	*

CENTRAL MOTEO	F.A.	SECTION	COUNTY	TOTAL	SHEET
GENERAL NOTES	PTE.	**	*	SHEETS	NO.
INC.293_(IL.199)			CONTRACT	NO.	72H28
OF SHEETS STA TO STA.		ILL INOIS FED. A	D PROJECT		
** MEREDOSIA BI	DCE TRE	E REM 2014		• PIKE	MORGAN