

URBAN

URBAN

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
				0005 80% FEDERAL 20% STATE	0021 80% FEDERAL 20% STATE	0021 100% CITY
* 87602000	PEDESTRIAN PUSH-BUTTON POST	EACH	2		2	
* 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	3		3	
* 87900200	DRILL EXISTING HANDHOLE	EACH	4		4	
⚠ * 88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1		1	
* 88040160	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	1		1	
⚠ * 88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	1		1	
* 88040290	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 5-SECTION, BRACKET MOUNTED	EACH	1		1	
⚠ * 88040110	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 4-SECTION, BRACKET MOUNTED	EACH	2		2	
* 88200410	TRAFFIC SIGNAL BACKPLATE, LOUVERED, FORMED PLASTIC	EACH	3		3	
⚠ * 88040120	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 4-SECTION, MAST ARM MOUNTED	EACH	2		2	
* 88600100	DETECTOR LOOP, TYPE I	FOOT	812		812	
* 88700200	LIGHT DETECTOR	EACH	4			4
* 88700300	LIGHT DETECTOR AMPLIFIER	EACH	1			1
* 88800100	PEDESTRIAN PUSH-BUTTON	EACH	2		2	
* 89100400	ILLUMINATED SIGN, LED	EACH	4		4	
⚠ * 89502210	MODIFY EXISTING CONTROLLER CABINET	EACH	1		1	
⚠ * 89502220	MODIFY EXISTING CONCRETE FOUNDATION	EACH	1		1	

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
				0005 80% FEDERAL 20% STATE	0021 80% FEDERAL 20% STATE	0021 100% CITY
* 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	852		852	
* 89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1		1	
* 89502380	REMOVE EXISTING HANDHOLE	EACH	2		2	
* 89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	2		2	
* X0323071	SPARE FULL ACTUATED CONTROLLER, SPECIAL	EACH	1		1	
X2501000	SEEDING, CLASS 2 (SPECIAL)	ACRE	0.2	0.2		
40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUND	2462	2462		
X6061300	CONCRETE MEDIAN, TYPE SB-6.06 (DOWELLED)	SQ FT	2776	2776		
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	28	28		
* X7830060	GROOVING FOR RECESSED PAVEMENT MARKING, LETTERS AND SYMBOLS	SQ FT	249.6	249.6		
* X7830070	GROOVING FOR RECESSED PAVEMENT MARKING 5"	FOOT	2920	2920		
* X7830074	GROOVING FOR RECESSED PAVEMENT MARKING 7"	FOOT	926	926		
* X7830076	GROOVING FOR RECESSED PAVEMENT MARKING 9"	FOOT	1073	1073		⚠

\* SPECIALTY ITEMS

⚠ REVISED 9-3-15

FILE NAME =	USER NAME = gstaffanck	DESIGNED -	REVISED -
o:\p\work\pvsdot\staffanck\02157883107	4282-ahtr-eod.dgn	DRAWN -	REVISED -
Default	PLOT SCALE = 1/8" = 1'-0"	CHECKED -	REVISED -
	PLOT DATE = 5/8/2014	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8379	(12RN	Effingham	36	5
			CONTRACT NO. 74282	
ILLINOIS FED. AID PROJECT				