

PAVEMENT MARKING SCHEDULE

STATION	TO	STATION	LENGTH FEET																	
				SHORT TERM PAVEMENT MARKING FT.	WORK ZONE PAVEMENT MARKING REMOVAL SQ. FT.	PAVEMENT MARKING REMOVAL SQ. FT.	GROOVING FOR RECESSED PAVEMENT MARKING, LETTERS, NUMBERS AND SYMBOLS SQ. FT.	MODIFIED URETHANE PAVEMENT MARKING - LETTERS AND SYMBOLS SQ. FT.	GROOVING FOR RECESSED PAVEMENT MARKING 5" FT.	MODIFIED URETHANE PAVEMENT MARKING - LINE 4" FT.	GROOVING FOR RECESSED PAVEMENT MARKING 7" FT.	MODIFIED URETHANE PAVEMENT MARKING - LINE 6" FT.	GROOVING FOR RECESSED PAVEMENT MARKING 9" FT.	MODIFIED URETHANE PAVEMENT MARKING - LINE 8" FT.	GROOVING FOR RECESSED PAVEMENT MARKING 13" FT.	MODIFIED URETHANE PAVEMENT MARKING - LINE 12" FT.	GROOVING FOR RECESSED PAVEMENT MARKING 25" FT.	MODIFIED URETHANE PAVEMENT MARKING - LINE 24" FT.	RAISED REFLECTIVE PAVEMENT MARKER EACH	PRISMATIC CURB REFLECTORS EACH
32+05	TO	33+61	156	109	12				780	780			32	32	44	44			10	
33+61	TO	35+25	164	796	88		46.8	46.8	491	491			324	324	33	33	33	33	20	
35+25	TO	36+71	146																	
36+71	TO	38+96	225	939	104		109.2	109.2	618	618	448	448					36	36	14	24
38+96	TO	39+71	75	74	8		31.2	31.2	225	225	75	75							3	6
39+71	TO	42+50	279	711	80		62.4	62.4	806	806	223	223								28
WEST LEG OF RICKELMAN						725							717	717			25	25		
EAST LEG OF RICKELMAN						220				180	180					41	41			
PROJECT TOTALS			1,045	2,629	292	945	249.6	249.6	2,920	2,920	926	926	1,073	1,073	77	77	135	135	47	58

626' YELLOW
2003' WHITE

834' WHITE
2086' YELLOW

WHITE

33' WHITE
44' YELLOW

WHITE

27 ONE-WAY CRYSTAL
10 ONE-WAY AMBER
10 TWO-WAY AMBER

AMBER

PAVING SCHEDULE

STATION	TO	STATION	LENGTH FEET	WIDTH FEET	AREA SQ YD	BITUMINOUS MATERIALS (PRIME COAT) POUND	HOT MIX ASPHALT SURFACE REMOVAL 1 1/2" SQ YD	POLYMERIZED HOT MIX ASPHALT SURFACE COURSE, MIX "D", N90 TON	TEMPORARY RAMP SQ YD
32+05	TO	42+50	1,045	VAR.	5,472	2,462	5,472	460	151

EARTHWORK SCHEDULE

LOCATION	EARTH EXCAVATION CU. YD.	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE CU. YD.	EMBANKMENT CU. YD.	EARTHWORK BALANCE WASTE (+) SHORTAGE (-) CU. YD.	TOPSOIL FURNISH AND PLACE 4" SQ. YD.
LT. STA. 36+15 TO 42+10	236	175	356	-181	985

FURNISHING AND ERECTING RIGHT OF WAY MARKERS
55.00' LT. STA. 41+49.20 1 EACH

PCC PAVEMENT 10"
LT. STA. 36+13 TO 40+69 564 S. Y.

PROTECTING OR RESETTING SURVEY MARKERS
60.00' LT. STA. 36+47.56 1 EACH
55.00' LT. STA. 36+75.00 1 EACH
55.00' LT. STA. 37+70.68 1 EACH
55.00' LT. STA. 39+75.00 1 EACH
45.00' LT. STA. 40+75.00 1 EACH
45.00' LT. STA. 41+00.00 1 EACH

COMB. CONC. CURB & GUTTER, TYPE B6.24
LT. STA. 36+15 TO 42+07 637 FEET

CONC. MEDIAN, TYPE SB-6.06 (DOWELLED)
STA. 36+71.5 TO 42+30.1 2776 S. F.

9-3-14 REVISED SHEET