

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	STATE URBAN FOUR-LANE ROADWAY 100% STATE 0014	URBAN 0044 DRAINAGE SYSTEM 100% CITY OF DECATUR
50104701	REMOVAL OF EXISTING CONCRETE DECK NO. 1	EACH	1	1	
50104702	REMOVAL OF EXISTING CONCRETE DECK NO. 2	EACH	1	1	
50200100	STRUCTURE EXCAVATION	CU YD	92	92	
50300100	FLOOR DRAINS	EACH	116	116	
50300225	CONCRETE STRUCTURES	CU YD	46.2	46.2	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	1401.2	1401.2	
50300260	BRIDGE DECK GROOVING	SQ YD	3238	3238	
50300300	PROTECTIVE COAT	SQ YD	4635	4635	
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	5854	5854	
50500505	STUD SHEAR CONNECTORS	EACH	6681	6681	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	334,665	334,665	
50900105	ALUMINUM RAILING, TYPE L	FOOT	507	507	
51500100	NAME PLATES	EACH	2	2	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	72	72	