



- SYMBOLS**
- DRUM
 - † SIGN
 - ⊥ TYPE III BARRICADE
 - ▨ WORK AREA
 - ➡ ARROW BOARD
 - ◁ TEMPORARY RAISED PAVEMENT MARKER CRYSTAL
 - ◄ TEMPORARY RAISED PAVEMENT MARKER AMBER

- GENERAL NOTES FOR STAGE CONSTRUCTION**
1. ALL SIGNAGE, SPACING, TRAFFIC CONTROL EQUIPMENT AND TEMPORARY PAVEMENT MARKINGS SHALL BE IN ACCORDANCE WITH THE LATEST VERSION OF HIGHWAY STANDARD 701601 AND SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE EACH FOR TRAFFIC CONTROL AND PROTECTION STANDARD 701601, SPECIAL.
 2. WORKER SIGNS WILL BE COVERED WHEN WORKERS NOT PRESENT.

FILE NAME = #FILE#	USER NAME = #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	STAGE III TRAFFIC CONTROL			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		DRAWN -	REVISED -		SCALE:	SHEET NO. 7 OF 9 SHEETS	STA.	TO STA.	710	(49-X-B-2)BR & (48BR)BR	MACON	144	28
		CHECKED -	REVISED -		CONTRACT NO. 74438								
		DATE -	REVISED -		ILLINOIS FED. AID PROJECT								