



12" DIA. AMBER LED
FLASHING BEACONS (TYP.) WITH
TUNNEL VISER AND BACKPLATE
TO BE FURNISHED AND INSTALLED
BY DMS SIGN MANUFACTURE
(INCLUDED IN THE COST OF
THE DMS SIGN)

PROPOSED DMS.

CCTV DOME CAMERA WITH PAN TILT ZOOM CAPABILITY

ALUMINUM MAST FOR CAMERA
MOUNTING
(MOUNT CAMERA AS HIGH AS
POSSIBLE)

POLE MOUNTED EQUIPMENT
CABINET, TYPE B

ELEVATION

CCTV CAMERA PLACEMENT (TYP.)
OVERHEAD SIGN STRUCTURES (TYP.)

NOTES:

* THE CONTRACTOR SHALL SUBMIT COMPLETE ELECTRICAL DESIGN DETAILS AND CALCULATIONS SEALED BY AN ILLINOIS LICENSED ELECTRICAL AND STRUCTURAL ENGINEER TO THE RESIDENT ENGINEER FOR REVIEW AND APPROVAL PRIOR TO THE ORDERING OF ANY MATERIALS.

FILE NAME =	USER NAME = steffenmk	DESIGNED -	REVISED -
ct:\pw\work\p\idot\steffenmk\d0360593\074643-sht-dmsinstallationplan.dgn		DRAWN -	REVISED -
	PLOT SCALE = 5000.0000 ' / in.	CHECKED -	REVISED -
Default	PLOT DATE = 5/22/2014	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PROPOSED DMS & CCTV CAMERA DETAIL FOR OVERHEAD SIGN STRUCTURE			
SCALE:	SHEET	OF	SHEETS
	STA.		TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR	D7 ITS 2014	*	72	18
* EFFINGHAM, CUMBERLAND CLARK & LAWRENCE ILLINOIS FED. AID PROJECT			CONTRACT NO. 74643	