



12" DIA. AMBER LED
FLASHING BEACONS (TYP.) WITH
TUNNEL VISER AND BACKPLATE
TO BE FURNISHED AND INSTALLED
BY DMS SIGN MANUFACTURE
(INCLUDED IN THE COST OF
THE DMS SIGN)

ALUMINUM MAST FOR CAMERA
MOUNTING
(MOUNT CAMERA AS HIGH AS
POSSIBLE)

PROPOSED DMS.

POLE MOUNTED EQUIPMENT
CABINET, TYPE B

ELEVATION

**CCTV CAMERA PLACEMENT (TYP.)
BUTTERFLY SIGN STRUCTURE**

NOTES:

THE CONTRACTOR SHALL SUBMIT COMPLETE ELECTRICAL DESIGN DETAILS AND CALCULATIONS
SEALED BY AN ILLINOIS LICENSED ELECTRICAL AND STRUCTURAL ENGINEER
TO THE RESIDENT ENGINEER FOR REVIEW AND APPROVAL PRIOR
TO THE ORDERING OF ANY MATERIALS.

FILE NAME =	USER NAME = steffenmk	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PROPOSED DMS & CCTV CAMERA DETAIL FOR BUTTERFLY TRUSS SIGN STRUCTURE	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ci:\pw\work\p\idot\steffenmk\d0360593\074643-sht-dmsinstallationplan.dgn		DRAWN -	REVISED -			VAR	D7 ITS 2014	*	72	20	
Default	PLOT SCALE = 5000.0000' / in.	CHECKED -	REVISED -			* EFFINGHAM, CUMBERLAND		CONTRACT NO. 74643			
	PLOT DATE = 5/22/2014	DATE -	REVISED -			SCALE:	SHEET OF SHEETS	STA. TO STA.	CLARK & LAWRENCE ILLINOIS FED. AID PROJECT		