

RURAL  
CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	80% - 20% Federal	100% State	BRIDGE	BRIDGE	BRIDGE	BRIDGE	BRIDGE	BRIDGE	BRIDGE	BRIDGE	
				ROADWAY	ROADWAY	0014	0014	0014	0014	0014	0014	0014	0014	0014
				0004	0004	S. N. 0025, 0026	S. N. 0027, 0028	S. N. 0029, 0030	S. N. 0031	S. N. 0032	S. N. 0108	S. N. 0151	S. N. 0164	S. N. 0174
28100105	STONE RIPRAP, CLASS A3	SQ YD	11										11	
28100107	STONE RIPRAP, CLASS A4	SQ YD	514					514						
28100109	STONE RIPRAP, CLASS A5	SQ YD	3832			780	3052							
28100209	STONE RIPRAP, CLASS A5	TON	3846	3846										
28200200	FILTER FABRIC	SQ YD	6238	3806		780	1232	420						
31100910	SUBBASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	21333	21333										
31200500	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4"	SQ YD	21333	21333										
35501326	HOT-MIX ASPHALT BASE COURSE, 10 1/2"	SQ YD	7778	7778										
35501334	HOT-MIX ASPHALT BASE COURSE, 12 1/2"	SQ YD	1111	1111										
35501336	HOT-MIX ASPHALT BASE COURSE, 13"	SQ YD	9956	9956										
35501343	HOT-MIX ASPHALT BASE COURSE, 15"	SQ YD	1422	1422										
40600990	TEMPORARY RAMP	SQ YD	4089	4089										
40603153	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	77306	77306										
42100100	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT, 8"	SQ YD	21333	21333										

FILE NAME *	USER NAME * hoffmanj	DESIGNED -	REVISED -
c:\pwwork\pwwork\hoffmanj\08279918\087	713-sht-500.dgn	DRAWN -	REVISED -
	PLOT SCALE * 100.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE * 6/27/2014	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 2 OF 11 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FAI 70	60-III, 12RS-3	MADISON	242	4
CONTRACT NO. 76F13			ILLINOIS FED. AID PROJECT	