

RURAL  
CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	80%-20% Federal ROADWAY	100% State ROADWAY	BRIDGE	BRIDGE	BRIDGE	BRIDGE	BRIDGE	BRIDGE	BRIDGE	BRIDGE
				0004 RURAL	0004 RURAL	0014 S. N. 0025, 0026	0014 S. N. 0027, 0028	0014 S. N. 0029, 0030	0014 S. N. 0031	0014 S. N. 0032	0014 S. N. 0108	0014 S. N. 0151	0014 S. N. 0164
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	565	565									
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	942	942									
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	39	39									
78300100	PAVEMENT MARKING REMOVAL	SO FT	14624	14624									
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	2640	2640									
X0323583	SPEED INDICATOR SIGN	CAL DA	260	260									
X0326208	ALTERNATE ROUTE SIGNING	L SUM	1	1									
X0550300	SLOPE WALL BREAKING	SO YD	1820				1820						
X5010523	REMOVE CONCRETE END SECTION	EACH	5	5									
X5870015	BRIDGE DECK CONCRETE SEALER	SO FT	73868			15120	10280	8310	6550	6500	9185	9333	8590
X6350120	DELINEATOR REMOVAL	EACH	496	496									
X6430110	REMOVE IMPACT ATTENUATORS, SALVAGE	EACH	8	8									
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1									
X7010410	SPEED DISPLAY TRAILER	CAL MO	12	12									
X8570000	SMART TRAFFIC MONITORING SYSTEM	L SUM	1	1									

\* SPECIALTY ITEM

FILE NAME *	USER NAME * hoffmanj	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
cd:\pwwork\pwwork\hoffmanj\08279918\08279913-sht-500.dgn		DRAWN -	REVISED -						FAT 70	60-111, 121RS-3	MADISON	242	11
PLOT SCALE * 1/8"=1'-0"		CHECKED -	REVISED -		SCALE: SHEET 9 OF 11 SHEETS STA. TO STA.				CONTRACT NO. 76F13				
PLOT DATE * 6/27/2014		DATE -	REVISED -		ILLINOIS FED. AID PROJECT								