

PATCHING SCHEDULE											
DIR	STATION to STATION	LOCATION DL/PL	DIMENSIONS		CLASS A PATCHES, 13"				SAW CUTS	TIE BARS 3/4"	PATCHING REINFORCEMENT
			L TH	WTH	TY-I	TY-II	TY-III	TY-IV			
			FT	FT	SO YDS	SO YDS	SO YDS	SO YDS			
WB	1016+51 - 1016+57	DL	6	12		8			60		8
WB	1017+51 - 1017+57	PL	6	12		8			60		8
WB	1017+51 - 1017+57	DL	6	12		8			60		8
WB	1035+65 - 1035+71	DL	6	12		8			60		8
WB	1036+12 - 1036+18	PL	6	12		8			60		8
WB	1036+12 - 1036+18	DL	6	12		8			60		8
WB	1037+65 - 1037+71	PL	6	12		8			60		8
WB	1037+65 - 1037+71	DL	6	12		8			60		8
WB	1038+13 - 1038+19	DL	6	12		8			60		8
WB	1068+74 - 1068+80	PL	6	12		8			60		8
WB	1068+74 - 1068+80	DL	6	12		8			60		8
WB	1135+62 - 1135+87	DL	25	12			33		98	13	33
WB	1300+12 - 1300+20	DL	8	12		11			64		11
WB	1415+17 - 1415+27	DL	10	6		7			44		7
WB	1427+26 - 1427+36	DL	10	12		13			68		13
WB	1442+72 - 1442+78	DL	6	12		8			60		8
WB	1442+72 - 1442+78	DL	6	12		8			60		8
WB	1477+59 - 1477+65	DL	6	12		8			60		8
WB	1481+59 - 1481+89	DL	30	12			40		108	15	40
WB	1482+08 - 1482+33	DL	25	12			33		98	13	33
WB	1491+68 - 1491+76	DL	8	12		11			64		11
WB	1500+50 - 1500+58	DL	8	6		5			40		5
WB	1505+98 - 1506+18	DL	20	6		13			64		13
WB	1506+23 - 1506+43	DL	20	6		13			64		13
WB	1506+99 - 1507+05	DL	6	12		8			60		8
WB	1510+58 - 1510+64	DL	6	12		8			60		8
WB	1575+80 - 1576+00	DL	20	6		13			64		13
SUBTOTAL (WB)					0	214	0	106	1736	41	320
SUBTOTAL (EB1+EB2+WB)					4	567	190	479	5844	245	1240
12% SUBTOTAL (EB1+EB2+WB)*					0	68	23	57	701	29	149
TOTAL					4	635	213	536	6545	274	1388

*NOTE: AN ADDITIONAL 12% HAS BEEN ADDED TO THE FINAL PATCHING QUANTITIY TO ALLOW FOR WINTER DAMAGE.