

PAVEMENT MARKING SCHEDULE								
STATION TO STATION	LTH	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	CRYSTAL RAISED REFLECTIVE PAVEMENT MARKERS	AMBER RAISED REFLECTIVE PAVEMENT MARKERS	PREFORMED PLASTIC PAVEMENT MARKING TY, B, INLAID			
					6" SOLID YELLOW	6" SKIP-DASH WHITE	6" SOLID WHITE	8" SOLID WHITE
	FT	EACH	EACH	EACH	FOOT	FOOT	FOOT	FOOT
MAINLINE								
EAST BOUND								
1028+40 - 1083+86	5546	136	136		5546	1387	5546	
1083+86 - 1093+86	1000	28	28		1000	250	1000	
1093+86 - 1107+92	1406	36	36		1406	351	1406	
1109+79 - 1127+33	1755	44	44		1755	439	1755	
1128+51 - 1160+40	3189	80	80		3189	797	3189	
1161+34 - 1222+53	6119	152	152		6119	1530	5439	
1222+53 - 1232+53	1000	28	28		1000	250	1000	
1232+53 - 1288+05	5552	140	140		5552	1388	4614	
1288+05 - 1298+05	1000	26	26		1000	250	1000	
1298+05 - 1359+26	6121	156	156		6121	1530	6121	
1360+73 - 1402+67	4194	104	104		4194	1048	3517	
1402+67 - 1412+67	1000	28	28		1000	250	1000	
1412+67 - 1427+89	1522	40	40		1522	380	572	
1503+23 - 1588+00	8477	212	212		8477	2119	8477	
WESTBOUND								
1028+40 - 1084+06	5566	136	136		5566	1392	5566	
1084+06 - 1094+06	1000	28	28		1000	250	1000	
1094+06 - 1107+92	1386	36	36		1386	346	1386	
1109+79 - 1127+33	1755	44	44		1755	439	1755	
1128+51 - 1160+40	3189	80	80		3189	797	3189	
1161+34 - 1222+54	6120	152	152		6120	1530	5160	
1222+54 - 1232+54	1000	28	28		1000	250	1000	
1232+54 - 1288+46	5592	140	140		5592	1398	4932	
1288+46 - 1298+46	1000	28	28		1000	250	1000	
1298+46 - 1366+04	6758	168	168		6758	1690	6758	
1367+51 - 1393+51	2600	68	68		2600	650	1699	
1395+02 - 1402+59	757	20	20		757	189	710	
1402+59 - 1412+59	1000	28	28		1000	250	1000	
1412+59 - 1427+89	1530	40	40		1530	382	850	
1503+23 - 1588+00	8477	212	212		8477	2119	8477	
IL 4 - GORES								
EB EXIT	1416	50	50	12	1416		1416	305
EB ENTRANCE	988				988		988	305
WB ENTRANCE	1088				1088		1088	305
WB EXIT	1336	56	56	11	1336		1336	305
IL 143 - GORES/RAMPS								
EB ENTRANCE					1000		2135	303
EB EXIT		52	52	12	1335		2143	303
WB ENTRANCE					1100		2288	303
WB EXIT		64	64	15	1963		2137	307
SUBTOTAL		2640	2640	50	105836	23821	102649	2436
TOTAL		2640	2690		220425			2436

AERIAL SPEED CHECK PAVEMENT MARKING SCHEDULE		
LOCATION	EB/WB	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID LINE 18"
STA.		FOOT
1030+45	EB/WB	24
1037+05	EB/WB	24
1331+10	EB	12
1337+70	EB	12
1536+63	WB	12
1543+23	WB	12
TOTAL:		96

PAINT CURB SCHEDULE	
LOCATION	LENGTH FT
IL 4 EB EXIT	65
IL 4 WB EXIT	65
IL 143 EB EXIT	50
IL 143 WB EXIT	82
TOTAL	262

PRISMATIC CURB REFLECTOR SCHEDULE	
LOCATION	EACH
IL 4 EB EXIT	9
IL 4 WB EXIT	9
IL 143 EB EXIT	9
IL 143 WB EXIT	9
TOTAL	36

WRONG WAY TRAFFIC PAVEMENT MARKING SCHEDULE			
LOCATION	EB/WB	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B, INLAID LINE 24"	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B, INLAID LETTERS AND SYMBOLS
STATION		FOOT	SOFT
IL 4 RAMPS			
14+01	EB	17	
14+03	EB	18	
13+23	WB	18	
13+22	WB	18	
12+52	EB		24.3
13+94	EB		31.2
10+73	WB		24.3
13+12	WB		31.2
IL 143 RAMPS			
19+76	EB	17	
19+85	EB	17	
20+15	WB	20	
20+17	WB	18	
18+26	EB		24.3
19+67	EB		31.2
18+65	WB		24.3
20+08	WB		31.2
TOTAL:		143	222

NOTE: ADDITIONAL QUANTITY OF PREFORMED PLASTIC PAVEMENT MARKING, TY B, INLAID - LETTERS & SYMBOLS IS INCLUDED IN THE PIPE UNDERDRAIN SCHEDULE.