

TREE REMOVAL- ALONG I-70 WESTBOUND SCHEDULE						
LOCATION			TREE REMOVAL (6 TO 15 UNITS DIAMETER)	TREE REMOVAL (OVER 15 UNITS DIAMETER)	SELECTIVE CLEARING	NOTES
STA.	LT/RT	REFERENCE POINT	UNIT	UNIT	ACRE	
1109+00	RT	SN 060-0026			0.5	15' FROM EDGE OF SHOULDER, FROM 600' BEFORE TO 600' AFTER SN 060-0026
1307+22	RT	AHEAD OF BLUE PANEL SIGN	6	34		3 TRUNKS AT 9, 12 and 13 UNITS EACH
1345+78	RT			22		SINGLE BASE WITH 2 TRUNKS AT 10 and 12 UNITS EACH
				18		SINGLE BASE WITH 2 TRUNKS AT 6 and 12 UNITS EACH
1364+00	RT	BEHIND BLUE PANEL SIGN	15			
1361+72	RT			29		
1372+00	RT		9			
TOTAL			30	103	0.5	

TREE REMOVAL FOR CHANNEL RE-ESTABLISHMENT SCHEDULE				
LOCATION			LT/RT	TREE REMOVAL
STA.	TO	STA.		ACRE
12+38.13	TO	14+49.68	LT	0.202
15+58.87	TO	15+75.00	LT	0.002
15+52.38	TO	15+75.00	RT	0.003
TOTAL				0.207

NOTES:

- 1 ALL TREES AND SHRUBS IN CLEAR ZONE, OBSTRUCTING DRAINAGE, OR OVERHANGING PAVEMENT SHALL BE REMOVED.
- 2 THE LOCATION STATIONS, TREE DIAMETERS, AND AREAS ARE APPROXIMATE. EXACT LOCATIONS TO BE DETERMINED BY THE ENGINEER.
- 3 TREE REMOVAL UNITS MEASUREMENTS WERE TAKEN AT TREE TRUNKS AT APPROXIMATELY 4' ABOVE GROUND LEVEL AT TREE BASE.
- 4 TREES OBSTRUCTING SIGNS, LOCATED OFF RIGHT-OF-WAY OR IN FENCE LINE, SHALL BE PRUNED TO MAXIMIZE SIGN VISIBILITY.
- 5 ALL TREES AND SHRUBS BETWEEN THE EDGE OF SHOULDER TO THE ROW FENCE IN THE AREA 600' BEFORE AND 100' AFTER ROADSIDE SIGNS ARE TO BE REMOVED.

CONCRETE END SECTION SCHEDULE									
DIR	STATION	SIZE	SHOULDER	MEDIAN	REMOVE CONCRETE END SECTION	CONCRETE END SECTION, STD 542001, 30" 1:6	CONCRETE END SECTION, STD 542001, 24" 1:6	CONCRETE END SECTION, STD 542001, 24" 1:4	CONCRETE COLLAR
		IN			EACH	EACH	EACH	EACH	CU YD
EB	1101+55	30	X		1	1			0.2
WB	1193+50	24	X		1		1		0.2
EB	1237+00	24	X		1		1		0.2
WB	1245+00	24	X		1		1		0.2
EB	1505+50	24		X	1			1	0.2
TOTAL					5	1	3	1	1

NOTE: A QUANTITY OF CONCRETE COLLAR HAS BEEN ADDED ABOVE IF NEEDED FOR CONCRETE END SECTIONS.