

TEMPORARY TRAFFIC CONTROL SCHEDULE FOR I-70 PAVEMENT RECONSTRUCTION WORK UNDER BRIDGES										
PAVEMENT REPLACEMENT LOCATION	STATION TO STATION	CONSTRUCTION STAGE	PAVEMENT MARKING REMOVAL	WORK ZONE PAVEMENT MARKING REMOVAL	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	GUARDRAIL MARKERS, TYPE A	BARRIER WALL MARKERS, TYPE C	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3
			SQ FT	SQ FT	FOOT	FOOT		EACH	EACH	EACH
I-70 EB UNDER OLD STAUNTON RD	1083+86 - 1093+86	2	928	2200	1225		10	49	1	
		3		2159		1213	12	49		1
I-70 WB UNDER OLD STAUNTON RD	1084+06 - 1094+06	2	928	2200	1225		10	49	1	
		3		2159		1213	12	49		1
I-70 EB UNDER MARINE RD	1288+05 - 1298+05	2	928	2200	1225		10	49	1	
		3		2159		1213	13	49		1
I-70 WB UNDER MARINE RD	1288+46 - 1298+46	2	928	2200	1225		10	49	1	
		3		2159		1213	19	49		1
I-70 EB UNDER IL-4	1222+53 - 1232+53	2	1631	3505	1225		10	49	1	
		3		2159		1213	10	49		1
I-70 WB UNDER IL-4	1222+54 - 1232+54	2	1532	3318	1225		10	49	1	
		3		2159		1213	10	49		1
I-70 EB UNDER IL-143	1402+67 - 1412+67	2	1518	3275	1225		10	49	1	
		3		2159		1213	13	49		1
I-70 WB UNDER IL-143	1402+59 - 1412+59	2	1334	3020	1225		10	49	1	
		3		2159		1213	10	49		1
TOTAL			9727	39190	9800	9704	179	780	8	8

TEMPORARY TRAFFIC CONTROL FOR I-70 SCHEDULE			
LOCATION	STATION TO STATION	PAVEMENT MARKING TAPE, TYPE III 8" BLACK	WORK ZONE PAVEMENT MARKING REMOVAL
		LN FT	SQ FT
CONSTRUCTION EB	1250+00 - 1265+00	3375	2250
CONSTRUCTION WB	1265+00 - 1280+00	3375	2250
TOTAL		6750	4500

TEMPORARY TRAFFIC CONTROL SCHEDULE FOR BRIDGE WORK													
BRIDGE LOCATION	STRUCTURE NUMBER	CONSTRUCTION STAGE	PAVEMENT MARKING REMOVAL	WORK ZONE PAVEMENT MARKING REMOVAL	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	GUARDRAIL MARKERS, TYPE A	BARRIER WALL MARKER, TYPE C	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	TEMPORARY BRIDGE TRAFFIC SIGNAL	TEMPORARY RUMBLE STRIPS	THERMOPLASTIC PAVEMENT MARKING, 6"
			SQ FT	SQ FT	FOOT	FOOT		EACH	EACH	EACH	EACH	EACH	FOOT
MARINE ROAD OVER I-70	SN 060-0164	2	1080	740	437.5				2		1	3	
		3	400	866		437.5				2		3	2960
I-70 EB OVER SILVER CREEK	SN 060-0025	2	419	1363	400		18	23	1				
		3	200	1363		400	13	23		1			
I-70 WB OVER SILVER CREEK	SN 060-0026	2	419	1363	400		18	23	1				
		3	200	1363		400	13	23		1			
I-70 EB OVER BRANCH OF SILVER CREEK	SN 060-0029	2	362	1271	308		20	9	1				
		3	154	1271		308	17	9		1			
I-70 WB OVER BRANCH OF SILVER CREEK	SN 060-0030	2	362	1271	308		19	9	1				
		3	154	1271		308	17	9		1			
I-70 EB OVER SUGAR CREEK	SN 060-0031	2	394	1323	360		23	9	1				
		3	180	1323		360	21	9		1			
I-70 WB OVER SUGAR CREEK	SN 060-0032	2	394	1323	360		20	9	1				
		3	180	1323		360	22	9		1			
TOTAL			4897	17434	2574	2574	219	162	8	8	1	6	2960